

**Alabama Department of Transportation
Proposal Item Summary**

029. HSIP-I085(364)

LEE COUNTY

Contract Time: 55 Working Days

for constructing the Interstate Lighting Upgrades on I-85 at the Exit 58 Interchange in Opelika. Length 0.738 mi.

The Bracket Estimate on this project is from \$432,312 to \$528,381.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
600A000	1	LS	Mobilization
654A000	30	SQYD	Solid Sodding
665B001	1	Ton	Temporary Mulching
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 14,000.00)
740B000	1,352	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	4	Each	Portable Changeable Message Sign, Type 2
750B571	8	Each	Roadway Luminaire Assembly with One, LED Low Profile Underpass Pendant, 150 Watt Luminaire
750B602	2	Each	Roadway Luminaire Assembly with One, LED, 400 Watt Equivalent Luminaire
750C010	2	Each	Pole Foundation,Roadway
750E123	750	LF	Conduit, 3/4 Inch, Rigid Metallic
750F022	2,300	LF	Conductor, #10 AWG
750F024	1,260	LF	Conductor, #6 AWG
750G010	360	LF	Combined Duct And Cable,2 #6 AWG/ 1 #6 AWG GND
751D008	84	Each	Replace Breakaway Fuse Holder
751D009	84	Each	Replace Fuse In Pole Base
751D057	28	Each	Replace Pole Wiring Cables
751K000	32	Each	Replace Roadway Luminaire (Including All Mounting Appurtenances)
751K002	36	Each	Replace High Mast Luminaire (Including All Mounting Appurtenances)
751L022	36	Each	Remove Roadway Luminaire
751L025	4	Each	Remove Roadway Luminaire Assembly
751L036	60	Each	Remove High Mast Luminaire
751L045	28	Each	Remove Power Cord
751L047	36	Each	Remove Roadway Luminaire Lowering Device System
751M002	1	LS	Remove Conductors and Conduits
751N000	28	Each	Modification of Existing (Lighting Pole)