

**Alabama Department of Transportation
Proposal Item Summary**

043. STPMN-2619(252)

ELMORE COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Widening, Resurfacing, and Traffic Stripe on the Coosada Parkway from the junction of the Alabama River Parkway to the junction of SR-14 southwest of Elmore. Length 5.709 mi.

The Bracket Estimate on this project is from \$1,163,684 to \$1,422,280.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity Units	Description
206C010	48 SQYD	Removing Concrete Driveway
206E008	8 Each	Removing Guardrail End Anchor (All Type)
405A000	10,634 Gal	Tack Coat
407B000	6 Mile	Joint Sealant For Hot Mix Asphalt Pavement
410H000	1 Each	Material Remixing Device
424A366	9,421 Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	100 Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B662	983 Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	6 Mile	Scoring Bituminous Pavement Surface
430B043	1,106 Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1 LS	Mobilization
630A001	100 LF	Steel Beam Guardrail, Class A, Type 2
630C070	8 Each	Guardrail End Anchor, Type 10 Series
698A000	1 LS	Construction Fuel (Maximum Bid Limited to \$ 63,000.00)
701A231	12 Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	11 Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	2 Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701B205	400 LF	Dotted, Class 2, Type A, Traffic Stripe
701C000	4 Mile	Broken Temporary Traffic Stripe
701C001	34 Mile	Solid Temporary Traffic Stripe
701G144	400 LF	Solid White, Class W, Type A Traffic Stripe
701G152	400 LF	Solid Yellow, Class W, Type A Traffic Stripe
701G251	825 LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
701H001	108 LF	Solid Traffic Stripe Removed (Plastic)
701H002	800 LF	Solid Traffic Stripe Removed (Tape)
703A002	2,828 SQFT	Traffic Control Markings, Class 2, Type A
703B002	45 SQFT	Traffic Control Legends, Class 2, Type A
703C001	104 SQFT	Removal Of Existing Traffic Control Markings Or Legends (Plastic)
705A030	29 Each	Pavement Markers, Class A-H, Type 2-C
705A032	207 Each	Pavement Markers, Class A-H, Type 1-B
705A037	618 Each	Pavement Markers, Class A-H, Type 2-D
705A038	26 Each	Pavement Markers, Class A-H, Type 2-E
740B000	424 SQFT	Construction Signs
740D000	100 Each	Channelizing Drums
740E000	100 Each	Cones (36 Inches High)
740M001	100 Each	Ballast For Cone
740O000	1 Each	Pilot Car

Item No.	Quantity	Units	Description
741C010	1 Each		Portable Sequential Arrow And Chevron Sign Unit