

**Alabama Department of Transportation
Proposal Item Summary**

012. HSIP-0008(594)

MARENGO COUNTY

Contract Time: 100 Working Days

DBE Goal Percent: 7.00

for constructing the Restricted Crossing U-Turn Intersection on SR-8 (US-80) at SR-25 north of Faunsdale. Length 0.596 mi.

The Bracket Estimate on this project is from \$1,514,606 to \$1,851,186.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$36.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity Units	Description
201A002	1 LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 1 Acre)
206C002	119 SQYD	Removing Concrete Slope Paving
206D000	164 LF	Removing Pipe
206D007	210 LF	Removing Concrete Flume
206E001	5 Each	Removing Inlets
206E002	2 Each	Removing Junction Boxes
206E050	8 Each	Removing Slope Paved Headwall
210A000	4,110 CUYD	Unclassified Excavation
210D022	1,835 CUYD	Borrow Excavation (Loose Truckbed Measurement)(A-2-4(0) or A-4(0))
214A000	151 CUYD	Structure Excavation
214B001	57 CUYD	Foundation Backfill, Commercial
230A000	32 RBST	Roadbed Processing
301A012	7,694 SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A000	7,694 SQYD	Bituminous Treatment A
405A000	2,783 Gal	Tack Coat
407B000	2 Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	8,370 SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1 Each	Material Remixing Device
424A360	1,053 Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B651	1,274 Ton	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	75 Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B659	50 Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B681	1,298 Ton	Superpave Bituminous Concrete Lower Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424C360	1,322 Ton	Superpave Bituminous Concrete Base Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	1 Mile	Scoring Bituminous Pavement Surface
530A001	381 LF	18" Roadway Pipe (Class 3 R.C.)
530A104	19 LF	36" Roadway Pipe (Class 3 R.C.) (Extension)
530B013	12 LF	29" Span, 18" Rise Roadway Pipe (Class 3 R.C.) (Extension)
535B012	122 LF	29" Span, 18" Rise Side Drain Pipe
600A000	1 LS	Mobilization
610D003	1,000 SQYD	Filter Blanket, Geotextile
614A000	111 CUYD	Slope Paving
619A002	1 Each	18" Roadway Pipe End Treatment, Class 1
619B000	1 Each	17" Span, 13" Rise Roadway Pipe End Treatment, Class 1
619B117	8 Each	29" Span, 18" Rise Side Drain Pipe End Treatment, Class 1

Item No.	Quantity	Units	Description
620A000	1	CUYD	Minor Structure Concrete
621A019	2	Each	Junction Boxes, Type 1 Or 2P
621A057	1	Each	Junction Boxes, Type Partial
621C020	7	Each	Inlets, Type Y
621C027	1	Each	Inlets, Type C
621D019	7	Each	Inlet Units, Type Y
623B001	90	LF	Concrete Curb, Type N Special
650A000	150	CUYD	Topsoil
652A100	3	Acre	Seeding
652C000	15	Acre	Mowing
654A001	24,469	SQYD	Solid Sodding (Bermuda)
656A010	3	Acre	Mulching
665A000	6	Acre	Temporary Seeding
665B001	18	Ton	Temporary Mulching
665E000	1,000	SQYD	Polyethylene
665F000	200	Each	Hay Bales
665G000	150	Each	Sand Bags
665J002	1,003	LF	Silt Fence
665N000	400	Ton	Temporary Coarse Aggregate,ALDOT Number 1
665N001	200	Ton	Temporary Coarse Aggregate,ALDOT Number 4
665O001	1,003	LF	Silt Fence Removal
665P005	9	Each	Inlet Protection, Stage 3 Or 4
665Q002	540	LF	Wattle
666A001	3	Acre	Pest Control Treatment
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 78,000.00)
701A227	1	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	2	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,715	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C001	3	Mile	Solid Temporary Traffic Stripe
701D005	1	Mile	Solid Traffic Stripe Removed
703A002	8,086	SQFT	Traffic Control Markings, Class 2, Type A
703B002	362	SQFT	Traffic Control Legends, Class 2, Type A
703D001	409	SQFT	Temporary Traffic Control Markings
705A030	792	Each	Pavement Markers, Class A-H, Type 2-C
705A031	347	Each	Pavement Markers, Class A-H, Type 1-A
705A032	107	Each	Pavement Markers, Class A-H, Type 1-B
705A038	205	Each	Pavement Markers, Class A-H, Type 2-E
710A160	277	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)
710A170	377	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick (Type IV Background)
710B021	658	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
740B000	1,423	SQFT	Construction Signs
740D000	250	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740F002	10	Each	Barricades, Type III
740M001	200	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	4	Each	Portable Changeable Message Sign, Type 2
750B601	7	Each	Roadway Luminaire Assembly with One, LED, 250 Watt Equivalent Luminaire
750B602	5	Each	Roadway Luminaire Assembly with One, LED, 400 Watt Equivalent Luminaire
750C010	12	Each	Pole Foundation,Roadway
750G010	3,000	LF	Combined Duct And Cable,2 #6 AWG/ 1 #6 AWG GND