

**Alabama Department of Transportation
Proposal Item Summary**

022. IM-1065(507)

MONTGOMERY COUNTY

Contract Time: 55 Working Days

DBE Goal Percent: 3.00

for constructing the Pavement Preservation (Micro-Milling, Resurfacing, and Traffic Stripe) on I-65 from a point north of the Alabama River Bridge (MP 172.550) to the Elmore County Line. Length 4.649 mi.

The Bracket Estimate on this project is from \$1,273,327 to \$1,556,288.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
408B000	155,190	SQYD	Micro-Milling Existing Pavement (Approximately 0.00" Thru 1.00" Thick)
410H000	1	Each	Material Remixing Device
420A015	7,350	Ton	Polymer Modified Open Graded Friction Course
420B000	27,950	Gal	Open Graded Friction Course Tack Coat
424B283	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range E
424B287	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range E
432A000	78,260	SQYD	High Density Mineral Bond
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 75,000.00)
701A227	7	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	7	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	13	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B063	695	LF	Dotted, Class 2, Type A Traffic Stripe(Lane Drop 10" Wide)
701B207	2,532	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	26	Mile	Broken Temporary Traffic Stripe
701C001	28	Mile	Solid Temporary Traffic Stripe
701F000	5,064	LF	Dotted Temporary Traffic Stripe
701F010	1,390	LF	Dotted Temporary Traffic Stripe (Lane Drop)
701G142	32,000	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	16,010	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	16,010	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G161	32,000	LF	Broken Black, Class W, Type B Traffic Stripe (5" Wide)
701H001	32,020	LF	Solid Traffic Stripe Removed (Plastic)
701H006	32,000	LF	Broken Traffic Stripe Removed (Plastic)
703A002	5,104	SQFT	Traffic Control Markings, Class 2, Type A
703B002	41	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,522	SQFT	Temporary Traffic Control Markings
705A030	1,287	Each	Pavement Markers, Class A-H, Type 2-C
705A031	745	Each	Pavement Markers, Class A-H, Type 1-A
705A032	34	Each	Pavement Markers, Class A-H, Type 1-B
740B000	2,475	SQFT	Construction Signs
740C000	54	SQFT	Special Construction Signs
740D000	500	Each	Channelizing Drums
740E000	500	Each	Cones (36 Inches High)
740M001	500	Each	Ballast For Cone
741C010	4	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	8	Each	Portable Changeable Message Sign, Type 2