

**Alabama Department of Transportation
Proposal Item Summary**

036. NH-HSIP-0006(579)

TUSCALOOSA COUNTY

Contract Time: 110 Working Days

DBE Goal Percent: 3.00

for constructing the Safety Widening, Planing, Resurfacing, Guardrail Installation, and Traffic Stripe on SR-6 (US-82) from 1.000 mile east of the junction of Midway Drive to the Bibb County Line. Length 4.662 mi.

The Bracket Estimate on this project is from \$4,301,925 to \$5,257,909.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$23.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	3,188	LF	Removing Guardrail
206E008	6	Each	Removing Guardrail End Anchor (All Type)
305B079	11,443	Ton	Crushed Aggregate, Section 825, Type A, For Miscellaneous Use
405A000	34,579	Gal	Tack Coat
407B000	10	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	153,526	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	11,679	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	1,290	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	17,368	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B685	3,430	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B692	3,389	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	17	Mile	Scoring Bituminous Pavement Surface
430B050	100	Ton	Aggregate Surfacing (ALDOT#1)
600A000	1	LS	Mobilization
610D003	300	SQYD	Filter Blanket, Geotextile
630A001	3,188	LF	Steel Beam Guardrail, Class A, Type 2
630C001	3	Each	Guardrail End Anchor, Type 8
630C080	3	Each	Guardrail End Anchor, Type 20 Series (MASH)
665G000	200	Each	Sand Bags
665J002	660	LF	Silt Fence
665O001	660	LF	Silt Fence Removal
665Q002	2,500	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 231,500.00)
701A227	10	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	10	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	10	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	9,746	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	28	Mile	Broken Temporary Traffic Stripe
701C001	75	Mile	Solid Temporary Traffic Stripe
701F000	29,238	LF	Dotted Temporary Traffic Stripe
703A002	706	SQFT	Traffic Control Markings, Class 2, Type A
703B002	68	SQFT	Traffic Control Legends, Class 2, Type A
703D002	2,116	SQFT	Temporary Traffic Control Markings (Paint)

Item No.	Quantity	Units	Description
703E002	202	SQFT	Temporary Traffic Control Legends (Paint)
705A030	647	Each	Pavement Markers, Class A-H, Type 2-C
705A037	9	Each	Pavement Markers, Class A-H, Type 2-D
728A000	2	Each	Truck Mounted Impact Attenuator Unit
740B000	2,324	SQFT	Construction Signs
740D000	90	Each	Channelizing Drums
740E000	700	Each	Cones (36 Inches High)
740I005	2	Each	Warning Lights, Type B (Detachable Head)
740M001	700	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit