

**Alabama Department of Transportation
Proposal Item Summary**

040. RASTPNU-3318(251)

HALE COUNTY

Contract Time: 35 Working Days

DBE Goal Percent: 1.00

for constructing the Widening, Resurfacing, and Traffic Stripe on CR-44 from the junction of SR-69 to the junction of CR-50 southwest of Moundville. Length 4.746mi.

The Bracket Estimate on this project is from \$842,429 to \$1,029,636.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	11,138	Gal	Tack Coat
407B000	5	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A336	3,113	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range A/B
424B643	4,100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B647	975	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B670	500	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	1,379	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
665F000	60	Each	Hay Bales
665J002	2,500	LF	Silt Fence
665O001	2,500	LF	Silt Fence Removal
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 45,200.00)
701A030	10	Mile	Solid White, Class 2T, Type A Traffic Stripe
701A034	7	Mile	Solid Yellow, Class 2T, Type A Traffic Stripe
701A044	3	Mile	Broken Yellow, Class 2T, Type A Traffic Stripe
701C000	3	Mile	Broken Temporary Traffic Stripe
701C001	16	Mile	Solid Temporary Traffic Stripe
703A004	108	SQFT	Traffic Control Markings, Class 2T, Type A
705A032	65	Each	Pavement Markers, Class A-H, Type 1-B
705A037	450	Each	Pavement Markers, Class A-H, Type 2-D
740B000	489	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car