

**Alabama Department of Transportation
Proposal Item Summary**

041. RASTPNU-4119(252)

LEE COUNTY

Contract Time: 45 Working Days

DBE Goal Percent: 1.00

for constructing the Resurfacing (Full Depth Reclamation) and Traffic Stripe on CR-188 from the intersection of SR-14 to Sougahatchee Creek north of Loachapoka. Length 2.693 mi.

The Bracket Estimate on this project is from \$669,173 to \$817,878.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

| Item No. | Quantity | Units | Description |
|----------|----------|-------|--|
| 206C010 | 24 | SQYD | Removing Concrete Driveway |
| 210D021 | 100 | CUYD | Borrow Excavation (Loose Truckbed Measurement)(A4 or Better) |
| 302A001 | 35,972 | SQYD | Full Depth Reclamation, 8" thick |
| 302B000 | 719 | Ton | Portland Cement For Full Depth Reclamation |
| 401A000 | 34,923 | SQYD | Bituminous Treatment A |
| 401B108 | 34,352 | SQYD | Bituminous Treatment G (With Polymer Additive) |
| 405A000 | 57 | Gal | Tack Coat |
| 407B000 | 3 | Mile | Joint Sealant For Hot Mix Asphalt Pavement |
| 424A346 | 3,164 | Ton | Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B |
| 424A349 | 52 | Ton | Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B |
| 424B642 | 158 | Ton | Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B |
| 430B043 | 538 | Ton | Aggregate Surfacing (1" Down, Crusher Run) |
| 600A000 | 1 | LS | Mobilization |
| 652A100 | 1 | Acre | Seeding |
| 656A010 | 1 | Acre | Mulching |
| 665F000 | 50 | Each | Hay Bales |
| 665J002 | 500 | LF | Silt Fence |
| 665O001 | 500 | LF | Silt Fence Removal |
| 680A001 | 1 | LS | Geometric Controls |
| 698A000 | 1 | LS | Construction Fuel (Maximum Bid Limited to \$ 35,000.00) |
| 701A231 | 6 | Mile | Solid White, Class 2, Type A Traffic Stripe |
| 701A235 | 3 | Mile | Solid Yellow, Class 2, Type A Traffic Stripe |
| 701A245 | 2 | Mile | Broken Yellow, Class 2, Type A Traffic Stripe |
| 701C000 | 4 | Mile | Broken Temporary Traffic Stripe |
| 701C001 | 6 | Mile | Solid Temporary Traffic Stripe |
| 703A002 | 340 | SQFT | Traffic Control Markings, Class 2, Type A |
| 703D001 | 340 | SQFT | Temporary Traffic Control Markings |
| 705A032 | 100 | Each | Pavement Markers, Class A-H, Type 1-B |
| 705A037 | 156 | Each | Pavement Markers, Class A-H, Type 2-D |
| 740B000 | 657 | SQFT | Construction Signs |
| 740E000 | 25 | Each | Cones (36 Inches High) |
| 740F002 | 22 | Each | Barricades, Type III |
| 740I002 | 11 | Each | Warning Lights, Type B |
| 740M001 | 25 | Each | Ballast For Cone |
| 740O000 | 1 | Each | Pilot Car |