

**Alabama Department of Transportation
Proposal Item Summary**

045. RASTPOA-6116(253)

TALLADEGA COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Resurfacing and Traffic Stripe on CR-175 (Oakdale Road) from the junction of SR-21 northwest of Sycamore to the junction of SR-76 northeast of Childersburg. Length 5.589 mi.

The Bracket Estimate on this project is from \$843,037 to \$1,030,378.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$2.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	175	LF	Removing Guardrail
206E019	4	Each	Removing Guardrail End Anchor (Type 10)
401B108	70,828	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	2,146	Gal	Tack Coat
407B000	6	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A346	6,005	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B639	769	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	1,414	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630A021	76	LF	Steel Beam Guardrail, Class A, Type 2 (Steel Post)
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
630G003	119	LF	Steel Beam Guardrail for Culvert, Class A, Type 2, Case 3
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 48,000.00)
701A231	12	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	6	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	5	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	9	Mile	Broken Temporary Traffic Stripe
701C001	11	Mile	Solid Temporary Traffic Stripe
701G252	500	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide) (Rumble Strip)
703A002	172	SQFT	Traffic Control Markings, Class 2, Type A
705A032	169	Each	Pavement Markers, Class A-H, Type 1-B
705A037	468	Each	Pavement Markers, Class A-H, Type 2-D
740B000	395	SQFT	Construction Signs
740E000	25	Each	Cones (36 Inches High)
740M001	25	Each	Ballast For Cone
740O000	1	Each	Pilot Car