

**Alabama Department of Transportation
Proposal Item Summary**

048. STPAA-0068(508)

DEKALB AND MARSHALL COUNTIES

Contract Time: 65 Working Days

DBE Goal Percent: 6.00

for constructing the Resurfacing and Access Management on SR-68 from the junction of SR-75 (MP 0.000) to west of the junction of Juanita Drive in Crossville (MP 9.020). Length 9.020 mi.

The Bracket Estimate on this project is from \$2,036,407 to \$2,488,942.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206E039	1	Each	Removing Mailboxes (Including Reset With a New 2 Inch Metal Or 4 Inch Timber Post)
210A000	352	CUYD	Unclassified Excavation
405A000	15,541	Gal	Tack Coat
407B000	13	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B001	163,197	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	13,464	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424C364	5,531	Ton	Superpave Bituminous Concrete Base Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
430B043	4,715	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
614A000	28	CUYD	Slope Paving
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
665J002	340	LF	Silt Fence
665O001	340	LF	Silt Fence Removal
665Q002	200	LF	Wattle
666A001	5	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 109,700.00)
701A227	19	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	12	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	6	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,520	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	6	Mile	Broken Temporary Traffic Stripe
701C001	30	Mile	Solid Temporary Traffic Stripe
703A002	4,230	SQFT	Traffic Control Markings, Class 2, Type A
703B002	225	SQFT	Traffic Control Legends, Class 2, Type A
703D001	4,230	SQFT	Temporary Traffic Control Markings
705A030	84	Each	Pavement Markers, Class A-H, Type 2-C
705A032	1,041	Each	Pavement Markers, Class A-H, Type 1-B
705A037	873	Each	Pavement Markers, Class A-H, Type 2-D
705A038	396	Each	Pavement Markers, Class A-H, Type 2-E
707F001	86	Each	Flexible Delineator Post with Base, Yellow
740B000	979	SQFT	Construction Signs
740D000	200	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
740O000	1	Each	Pilot Car
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit