

**Alabama Department of Transportation
Proposal Item Summary**

050. STPAA-FMGR-0021(570)

LOWNDES COUNTY

Contract Time: 60 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, Guardrail Reset, Bridge Guardrail Retrofit, and Traffic Stripe on SR-21 from the Wilcox County Line to 0.500 mile south of the junction of CR-45. Length 10.940 mi.

The Bracket Estimate on this project is from \$2,442,470 to \$2,985,241.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206E008	42	Each	Removing Guardrail End Anchor (All Type)
210A000	215	CUYD	Unclassified Excavation
401B100	180,100	SQYD	Bituminous Treatment E (With Polymer Additive)
405A000	18,870	Gal	Tack Coat
407B000	11	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	188,700	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	14,875	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	695	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	520	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	21	Mile	Scoring Bituminous Pavement Surface
430B043	1,400	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
610D003	250	SQYD	Filter Blanket, Geotextile
629D003	12	Each	Bridge Guardrail Retrofit, Type SC
630C003	12	Each	Guardrail End Anchor, Type 13
630C080	30	Each	Guardrail End Anchor, Type 20 Series (MASH)
631C010	2,938	LF	Guardrail Reset
665G000	200	Each	Sand Bags
665J002	800	LF	Silt Fence
665O001	800	LF	Silt Fence Removal
665Q002	500	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 144,000.00)
701A227	22	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	14	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	5	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	10	Mile	Broken Temporary Traffic Stripe
701C001	72	Mile	Solid Temporary Traffic Stripe
701G146	903	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	903	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	1,805	LF	Solid Traffic Stripe Removed (Plastic)
703A002	454	SQFT	Traffic Control Markings, Class 2, Type A
703D001	414	SQFT	Temporary Traffic Control Markings
705A032	250	Each	Pavement Markers, Class A-H, Type 1-B
705A037	800	Each	Pavement Markers, Class A-H, Type 2-D

Item No.	Quantity	Units	Description
740B000	1,690	SQFT	Construction Signs
740D000	75	Each	Channelizing Drums
740E000	350	Each	Cones (36 Inches High)
740M001	350	Each	Ballast For Cone
740O000	1	Each	Pilot Car