

**Alabama Department of Transportation  
Proposal Item Summary**

**052. STPAA-HSIP-0003(627)**

**CHILTON COUNTY**

Contract Time: 55 Working Days

DBE Goal Percent: 1.00

for constructing the Safety Widening, Planing, Resurfacing, and Traffic Stripe on SR-3 (US-31) from the North City Limits of Thorsby to the North City Limits of Jemison. Length 3.758 mi.

The Bracket Estimate on this project is from \$1,429,152 to \$1,746,741.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$10.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C000	4	SQYD	Removing Concrete Sidewalk
206C010	112	SQYD	Removing Concrete Driveway
209A000	1	Each	Mailbox Reset, Single
212A000	279	STA	Machine Grading Shoulders
305B077	432	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	11,092	Gal	Tack Coat
407B000	5	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	65,236	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	7,237	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	362	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	4,048	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B662	1,103	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	6	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
618A000	5	SQYD	Concrete Sidewalk, 4" Thick
618C001	10	SQFT	Detectable Warning Surface
652A100	3	Acre	Seeding
654A000	8	SQYD	Solid Sodding
656A010	3	Acre	Mulching
665E000	100	SQYD	Polyethylene
665G000	100	Each	Sand Bags
665J002	330	LF	Silt Fence
665O001	330	LF	Silt Fence Removal
665Q002	400	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 77,000.00)
701A227	8	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	668	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	8	Mile	Broken Temporary Traffic Stripe
701C001	33	Mile	Solid Temporary Traffic Stripe
703A002	3,976	SQFT	Traffic Control Markings, Class 2, Type A
703A011	661	SQFT	Traffic Control Markings, Class W, Type A
703B002	633	SQFT	Traffic Control Legends, Class 2, Type A
703D001	3,070	SQFT	Temporary Traffic Control Markings

Item No.	Quantity	Units	Description
705A030	74	Each	Pavement Markers, Class A-H, Type 2-C
705A032	310	Each	Pavement Markers, Class A-H, Type 1-B
705A037	264	Each	Pavement Markers, Class A-H, Type 2-D
705A038	116	Each	Pavement Markers, Class A-H, Type 2-E
710A165	43	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background, Fluorescent)
710A170	70	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick (Type IV Background)
710B021	196	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
730H001	3,522	LF	Loop Wire
730I001	840	LF	Loop Detector Lead-In-Cable
730L002	50	LF	1", Metallic, Conduit
730L005	30	LF	2", Non-Metallic, Conduit
740B000	1,216	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740O000	1	Each	Pilot Car
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit