

**Alabama Department of Transportation
Proposal Item Summary**

053. STPAA-HSIP-0017(581)

PICKENS COUNTY

Contract Time: 50 Working Days

DBE Goal Percent: 1.00

for constructing the Safety Widening, Resurfacing, Scrub Seal, and Traffic Stripe on SR-17 from the junction of Beaver Creek Road to the Lamar County Line. Length 5.266 mi.

The Bracket Estimate on this project is from \$2,726,456 to \$3,332,335.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$11.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C010	11	SQYD	Removing Concrete Driveway
206D001	50	LF	Removing Guardrail
206E008	8	Each	Removing Guardrail End Anchor (All Type)
305B077	3,342	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	27,573	Gal	Tack Coat
407B000	6	Mile	Joint Sealant For Hot Mix Asphalt Pavement
410H000	1	Each	Material Remixing Device
424A356	4,924	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	127	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B002	6,042	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1/2" Maximum Aggregate Size mix, ESAL Range C/D
424B685	1,580	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B687	8,842	Ton	Superpave Bituminous Concrete Lower Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B692	2,165	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	16	Mile	Scoring Bituminous Pavement Surface
433A000	86,520	SQYD	Scrub Seal
600A000	1	LS	Mobilization
630A001	100	LF	Steel Beam Guardrail, Class A, Type 2
630C003	4	Each	Guardrail End Anchor, Type 13
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
654A000	100	SQYD	Solid Sodding
665J002	660	LF	Silt Fence
665O001	660	LF	Silt Fence Removal
665Q002	500	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 143,780.00)
701A227	11	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	8	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	13	Mile	Broken Temporary Traffic Stripe
701C001	89	Mile	Solid Temporary Traffic Stripe
701G146	408	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	204	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	408	LF	Solid Traffic Stripe Removed (Tape)
701H007	204	LF	Broken Traffic Stripe Removed (Tape)
703A002	1,418	SQFT	Traffic Control Markings, Class 2, Type A

Item No.	Quantity	Units	Description
703D001	2,048	SQFT	Temporary Traffic Control Markings
705A032	119	Each	Pavement Markers, Class A-H, Type 1-B
705A037	411	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,132	SQFT	Construction Signs
740D000	25	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car