

**Alabama Department of Transportation  
Proposal Item Summary**

**055. STPAA-HSIP-0171(517)**

**FAYETTE COUNTY**

Contract Time: 70 Working Days

DBE Goal Percent: 3.00

for constructing the Safety Widening, Planing, Resurfacing, and Traffic Stripe on SR-171 from the junction of Stough Road to the Marion County Line. Length 5.675 mi.

The Bracket Estimate on this project is from \$2,391,849 to \$2,923,371.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C010	172	SQYD	Removing Concrete Driveway
206D001	300	LF	Removing Guardrail
206E008	16	Each	Removing Guardrail End Anchor (All Type)
305B077	1,831	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	9,019	Gal	Tack Coat
407B000	13	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	95,756	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
408A053	7,289	SQYD	Planing Existing Pavement (Approximately 2.10" Thru 3.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	5,668	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	487	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B002	7,144	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1/2" Maximum Aggregate Size mix, ESAL Range C/D
424B657	1,762	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B685	895	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B692	2,384	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	17	Mile	Scoring Bituminous Pavement Surface
433A000	115,905	SQYD	Scrub Seal
600A000	1	LS	Mobilization
630A001	300	LF	Steel Beam Guardrail, Class A, Type 2
630C003	8	Each	Guardrail End Anchor, Type 13
630C080	8	Each	Guardrail End Anchor, Type 20 Series (MASH)
654A000	100	SQYD	Solid Sodding
665J002	660	LF	Silt Fence
665O001	660	LF	Silt Fence Removal
665Q002	500	LF	Wattle
666A001	1	Acre	Pest Control Treatment
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 127,300.00)
701A227	12	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	8	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	1	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	185	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	9	Mile	Broken Temporary Traffic Stripe
701C001	59	Mile	Solid Temporary Traffic Stripe

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
703A002	1,755	SQFT	Traffic Control Markings, Class 2, Type A
703B002	135	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,551	SQFT	Temporary Traffic Control Markings
705A030	10	Each	Pavement Markers, Class A-H, Type 2-C
705A032	253	Each	Pavement Markers, Class A-H, Type 1-B
705A037	567	Each	Pavement Markers, Class A-H, Type 2-D
705A038	51	Each	Pavement Markers, Class A-H, Type 2-E
740B000	1,120	SQFT	Construction Signs
740D000	200	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
740O000	1	Each	Pilot Car