

**Alabama Department of Transportation  
Proposal Item Summary**

**056. STPAA-HSIP-0241(503)**

**MARION COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Safety Widening, Planing, Resurfacing, and Traffic Stripe on SR-241 from the junction of SR-172 in Bear Creek to the Franklin County Line. Length 1.955 mi.

The Bracket Estimate on this project is from \$918,962 to \$1,123,176.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C010	11	SQYD	Removing Concrete Driveway
305B077	2,748	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	20,710	Gal	Tack Coat
407B000	2	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	29,944	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A340	2,851	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424A369	69	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B642	2,640	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B670	250	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B677	805	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	6	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
665J002	660	LF	Silt Fence
665O001	660	LF	Silt Fence Removal
665Q002	500	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 49,500.00)
701A227	4	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	2	Mile	Broken Temporary Traffic Stripe
701C001	30	Mile	Solid Temporary Traffic Stripe
703A002	130	SQFT	Traffic Control Markings, Class 2, Type A
703D001	390	SQFT	Temporary Traffic Control Markings
705A032	30	Each	Pavement Markers, Class A-H, Type 1-B
705A037	199	Each	Pavement Markers, Class A-H, Type 2-D
740B000	764	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	25	Each	Cones (36 Inches High)
740M001	25	Each	Ballast For Cone
740O000	1	Each	Pilot Car