

**Alabama Department of Transportation
Proposal Item Summary**

059. STPMN-0118(252)

AUTAUGA COUNTY

Contract Time: 45 Working Days

DBE Goal Percent: 3.00

for constructing the Resurfacing and Traffic Stripe on Upper Kingston Road from the junction of 7th Street to the North City Limits of Prattville (Site 1) and the Planing, Widening, Resurfacing, and Traffic Stripe on Martin Luther King, Jr. Drive from the junction of 7th Street to the junction of Powell Road in Prattville (Site 2). Length 3.916 mi.

The Bracket Estimate on this project is from \$848,123 to \$1,036,595.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$10.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C000	87	SQYD	Removing Concrete Sidewalk
206E039	5	Each	Removing Mailboxes (Including Reset With a New 2 Inch Metal Or 4 Inch Timber Post)
212A000	350	STA	Machine Grading Shoulders
301A029	600	SQYD	Crushed Aggregate Base Course, Type B, Yard Mixed, 6" Thick Compacted Thickness
405A000	7,418	Gal	Tack Coat
407B000	4	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	22,295	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A340	5,610	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B639	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B643	400	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B647	105	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
533B099	100	LF	29" Span, 18" Rise Storm Sewer Pipe (Class 3 R.C.)
600A000	1	LS	Mobilization
610D003	200	SQYD	Filter Blanket, Geotextile
618A000	31	SQYD	Concrete Sidewalk, 4" Thick
618C001	240	SQFT	Detectable Warning Surface
618D000	87	SQYD	Curb Ramp
620A000	1	CUYD	Minor Structure Concrete
621C015	1	Each	Inlets, Type S1 Or S3 (1 Wing)
621C030	1	Each	Inlets, Type "Special"
623C003	71	LF	Combination Curb & Gutter, Type C (Modified)
641S500	25	Each	Valve Box Reset
645K500	35	Each	Manhole Frame And Cover Reset
650A000	500	CUYD	Topsoil
652A100	3	Acre	Seeding
654A000	200	SQYD	Solid Sodding
656A010	3	Acre	Mulching
665G000	50	Each	Sand Bags
665J002	2,000	LF	Silt Fence
665O001	2,000	LF	Silt Fence Removal
665Q002	1,000	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 46,000.00)
701A227	5	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	8	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)

Item No.	Quantity	Units	Description
701B205	300	LF	Dotted, Class 2, Type A, Traffic Stripe
701C001	11	Mile	Solid Temporary Traffic Stripe
703A002	2,483	SQFT	Traffic Control Markings, Class 2, Type A
703B002	364	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,483	SQFT	Temporary Traffic Control Markings
703E001	342	SQFT	Temporary Traffic Control Legends
740B000	541	SQFT	Construction Signs
740D000	75	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car