

**Alabama Department of Transportation  
Proposal Item Summary**

---

**063. STPNU-3620(250)**

**JACKSON COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 5.00

for constructing the Resurfacing (Scrub Seal) and Traffic Stripe on CR-90 from the junction of SR-73 to the Georgia State Line. Length 1.875 mi.

The Bracket Estimate on this project is from \$405,574 to \$495,702.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C010	80	SQYD	Removing Concrete Driveway
405A000	2,420	Gal	Tack Coat
407B000	2	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A341	2,541	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B644	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424C344	400	Ton	Superpave Bituminous Concrete Base Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	380	Ton	Aggregate Surfacing (1" Down, Crusher Run)
433A000	24,200	SQYD	Scrub Seal
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 21,800.00)
701A231	4	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701C001	8	Mile	Solid Temporary Traffic Stripe
701G251	550	LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
703A002	296	SQFT	Traffic Control Markings, Class 2, Type A
705A037	248	Each	Pavement Markers, Class A-H, Type 2-D
740B000	480	SQFT	Construction Signs
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car