

**Alabama Department of Transportation
Proposal Item Summary**

066. STPOA-0021(516) & STPOA-0021(543)

CALHOUN COUNTY

Contract Time: 65 Working Days

DBE Goal Percent: 1.00

for constructing the Traffic Signal Upgrade (Grading, Drainage, Pavement, Traffic Signs, Traffic Signals and Traffic Stripe) on SR-21 at Baltzell Gate Road in Anniston (Site 1) and Traffic Signal Improvements on SR 21 at the intersection of Lenlock Lane in Anniston (Site 2). Length 0.142 mi.

The Bracket Estimate on this project is from \$497,198 to \$607,687.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C002	10	SQYD	Removing Concrete Slope Paving
206D000	22	LF	Removing Pipe
206D002	345	LF	Removing Curb
206D007	14	LF	Removing Concrete Flume
206E000	2	Each	Removing Headwalls
210A000	702	CUYD	Unclassified Excavation
210D000	437	CUYD	Borrow Excavation
301A012	175	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A000	175	SQYD	Bituminous Treatment A
405A000	18	Gal	Tack Coat
424A360	60	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A361	30	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B650	104	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B651	26	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424C360	128	Ton	Superpave Bituminous Concrete Base Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
430B043	63	Ton	Aggregate Surfacing (1" Down, Crusher Run)
530A102	42	LF	24" Roadway Pipe (Class 3 R.C.) (Extension)
600A000	1	LS	Mobilization
610D003	480	SQYD	Filter Blanket, Geotextile
614A000	19	CUYD	Slope Paving
619A003	2	Each	24" Roadway Pipe End Treatment, Class 1
620A000	1	CUYD	Minor Structure Concrete
621C027	1	Each	Inlets, Type C
623B000	304	LF	Concrete Curb, Type N
650A000	215	CUYD	Topsoil
652A100	2	Acre	Seeding
654A001	80	SQYD	Solid Sodding (Bermuda)
656A010	2	Acre	Mulching
665G000	300	Each	Sand Bags
665J002	300	LF	Silt Fence
665N000	100	Ton	Temporary Coarse Aggregate,ALDOT Number 1
665O001	300	LF	Silt Fence Removal
665Q002	224	LF	Wattle
680A001	1	LS	Geometric Controls

Item No.	Quantity	Units	Description
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 26,000.00)
701A227	1	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	1	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	560	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701G242	206	LF	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701G253	842	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701G256	639	LF	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701G265	444	LF	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701H000	1,151	LF	Solid Traffic Stripe Removed (Paint)
701H005	321	LF	Broken Traffic Stripe Removed (Paint)
703A002	1,781	SQFT	Traffic Control Markings, Class 2, Type A
703B002	263	SQFT	Traffic Control Legends, Class 2, Type A
703C000	856	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Paint)
703C001	44	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Plastic)
703D001	192	SQFT	Temporary Traffic Control Markings
705A004	18	Each	Pavement Markers, Class A, Type 2-C
705A005	12	Each	Pavement Markers, Class A, Type 2-D
705A030	5	Each	Pavement Markers, Class A-H, Type 2-C
705A037	6	Each	Pavement Markers, Class A-H, Type 2-D
710A165	60	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background, Fluorescent)
710A170	33	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick (Type IV Background)
710B021	132	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
730A000	1	LS	Removal Of Existing Traffic Control Unit (SR-21 at Baltzell Gate Road)
730A001	1	LS	Removal Of Existing Traffic Control Unit (SR-21 at Lenlock Lane)
730C000	1	LS	Furnishing And Installing Traffic Control Unit (SR-21 at Baltzell Gate Road)
730C001	1	LS	Furnishing And Installing Traffic Control Unit (SR-21 at Lenlock Lane)
730E000	8	Each	Metal Traffic Signal Pole Foundation
730G001	7	Each	Metal Traffic Signal Strain Pole
730K000	4	Each	Traffic Signal Junction Box
730L002	100	LF	1", Metallic, Conduit
730L005	400	LF	2", Non-Metallic, Conduit
730N010	3	Each	Luminaire Extension Assembly, 12 FT
730N010	4	Each	Luminaire Extension Assembly, 12 FT)
730P022	13	Each	Vehicular Signal Head, 12 Inch, 3 Section, Type LED
730Q011	4	Each	Pedestrian Signal Head, Type LED
730R022	2	Each	Controller Assembly, Type III, 8 Phase
730U015	1	LS	Video Detection System SR-21 at Baltzell Gate Road)
730U016	1	LS	Video Detection System SR-21 at Lenlock Lane)
740B000	1,100	SQFT	Construction Signs
740D000	150	Each	Channelizing Drums
740E000	90	Each	Cones (36 Inches High)
740M001	90	Each	Ballast For Cone
741C010	3	Each	Portable Sequential Arrow And Chevron Sign Unit
745A000	12	HOUR	Uniformed Police Officer