

**Alabama Department of Transportation
Proposal Item Summary**

067. STPOA-3519(253)

HOUSTON COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 5.00

for constructing the Resurfacing and Traffic Stripe on North Broad Street from the intersection of SR-12 (US-84) to the junction of Omussee Road (Site 1) and on Omussee Road from the junction of North Broad Street to the intersection of SR-52 (Columbia Highway) (Site 2). Length 3.277 mi.

The Bracket Estimate on this project is from \$542,003 to \$662,448.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
401A006	42,326	SQYD	Bituminous Treatment G
405A000	4,233	Gal	Tack Coat
407B000	4	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A340	3,278	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	2,116	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 30,300.00)
701C000	2	Mile	Broken Temporary Traffic Stripe
701C001	6	Mile	Solid Temporary Traffic Stripe
703D001	94	SQFT	Temporary Traffic Control Markings
703E001	138	SQFT	Temporary Traffic Control Legends
740B000	241	SQFT	Construction Signs
740O000	1	Each	Pilot Car