

**Alabama Department of Transportation
Proposal Item Summary**

071. STPPC-4119(253)

LEE COUNTY

Contract Time: 45 Working Days

DBE Goal Percent: 1.00

for constructing the Resurfacing (Full Depth Reclamation) and Traffic Stripe on CR-243 from the Russell County Line to the intersection of CR-248 in Smiths Station. Length 2.621 mi.

The Bracket Estimate on this project is from \$615,362 to \$752,109.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C010	90	SQYD	Removing Concrete Driveway
302A001	32,512	SQYD	Full Depth Reclamation, 8" thick
302B000	570	Ton	Portland Cement For Full Depth Reclamation
401A000	32,512	SQYD	Bituminous Treatment A
401B108	30,975	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	47	Gal	Tack Coat
407B000	3	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A346	2,610	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B700	130	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range A/B
430B043	795	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
665F000	50	Each	Hay Bales
665J002	250	LF	Silt Fence
665O001	250	LF	Silt Fence Removal
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 33,000.00)
701A231	6	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	2	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	3	Mile	Broken Temporary Traffic Stripe
701C001	8	Mile	Solid Temporary Traffic Stripe
703A002	112	SQFT	Traffic Control Markings, Class 2, Type A
703D001	112	SQFT	Temporary Traffic Control Markings
705A032	110	Each	Pavement Markers, Class A-H, Type 1-B
705A037	105	Each	Pavement Markers, Class A-H, Type 2-D
740B000	472	SQFT	Construction Signs
740E000	25	Each	Cones (36 Inches High)
740F002	12	Each	Barricades, Type III
740I002	6	Each	Warning Lights, Type B
740M001	25	Each	Ballast For Cone
740O000	1	Each	Pilot Car