

**Alabama Department of Transportation
Proposal Item Summary**

007. HRRR-2620(251)

ELMORE COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Safety Widening, Guardrail Installations, and Traffic Stripe on Burt Mill Road from the junction of Flat Rock Road to the junction of SR-14 in Tallassee. Length 4.096 mi.

The Bracket Estimate on this project is from \$235,201 to \$287,468.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C010	102	SQYD	Removing Concrete Driveway
206D001	228	LF	Removing Guardrail
206E008	4	Each	Removing Guardrail End Anchor (All Type)
405A000	121	Gal	Tack Coat
424B662	1,590	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
630A004	228	LF	Steel Beam Guardrail, Class B, Type 2
630C022	4	Each	Guardrail End Anchor, Type Special
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 12,300.00)
701A231	9	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	8	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
703A002	312	SQFT	Traffic Control Markings, Class 2, Type A
705A032	111	Each	Pavement Markers, Class A-H, Type 1-B
705A037	443	Each	Pavement Markers, Class A-H, Type 2-D
740B000	278	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car