

**Alabama Department of Transportation
Proposal Item Summary**

022. STPAA-HSIP-0041(520)

ESCAMBIA COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 4.00

for constructing the Planing, Resurfacing, Steel Blockout Replacement, and Traffic Stripe on SR-41 from the intersection of SR-3 (US-31) in Brewton to a point north of Burnt Corn Creek. Length 2.349 mi.

The Bracket Estimate on this project is from \$595,041 to \$727,272.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206E008	12	Each	Removing Guardrail End Anchor (All Type)
405A000	4,081	Gal	Tack Coat
407B000	5	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	40,814	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	3,165	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A363	100	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A366	100	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	202	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	60	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
630A001	300	LF	Steel Beam Guardrail, Class A, Type 2
630C003	8	Each	Guardrail End Anchor, Type 13
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
631C010	1,208	LF	Guardrail Reset
641S500	4	Each	Valve Box Reset
645K500	14	Each	Manhole Frame And Cover Reset
650A000	150	CUYD	Topsoil
652A100	1	Acre	Seeding
652C000	12	Acre	Mowing
654A001	626	SQYD	Solid Sodding (Bermuda)
656A010	1	Acre	Mulching
665J002	500	LF	Silt Fence
665O001	500	LF	Silt Fence Removal
665Q002	100	LF	Wattle
666A001	1	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 32,000.00)
701A227	5	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	159	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	2	Mile	Broken Temporary Traffic Stripe
701C001	25	Mile	Solid Temporary Traffic Stripe
701G146	1,222	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	611	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)

Item No.	Quantity	Units	Description
701G154	62	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	1,284	LF	Solid Traffic Stripe Removed (Tape)
701H007	611	LF	Broken Traffic Stripe Removed (Tape)
703A002	1,079	SQFT	Traffic Control Markings, Class 2, Type A
703B002	431	SQFT	Traffic Control Legends, Class 2, Type A
703D001	747	SQFT	Temporary Traffic Control Markings
703E001	226	SQFT	Temporary Traffic Control Legends
705A030	22	Each	Pavement Markers, Class A-H, Type 2-C
705A032	25	Each	Pavement Markers, Class A-H, Type 1-B
705A037	153	Each	Pavement Markers, Class A-H, Type 2-D
740B000	954	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone