

**Alabama Department of Transportation  
Proposal Item Summary**

---

**025. STPMN-0120(250)**

**AUTAUGA COUNTY**

Contract Time: 30 Working Days

for constructing the Resurfacing and Traffic Stripe on CR-85 from the junction of CR-40 to a point south of Mortar Creek. Length 2.101 mi.

The Bracket Estimate on this project is from \$242,875 to \$296,848.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
405A000	2,600	Gal	Tack Coat
407B000	3	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A346	2,107	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B700	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range A/B
600A000	1	LS	Mobilization
650A000	300	CUYD	Topsoil
652A100	3	Acre	Seeding
656A010	3	Acre	Mulching
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 13,000.00)
701A030	5	Mile	Solid White, Class 2T, Type A Traffic Stripe
701A034	3	Mile	Solid Yellow, Class 2T, Type A Traffic Stripe
701A044	2	Mile	Broken Yellow, Class 2T, Type A Traffic Stripe
701C000	4	Mile	Broken Temporary Traffic Stripe
701C001	7	Mile	Solid Temporary Traffic Stripe
703A004	72	SQFT	Traffic Control Markings, Class 2T, Type A
705A032	59	Each	Pavement Markers, Class A-H, Type 1-B
705A037	204	Each	Pavement Markers, Class A-H, Type 2-D
740B000	214	SQFT	Construction Signs
740E000	25	Each	Cones (36 Inches High)
740M001	25	Each	Ballast For Cone
740O000	1	Each	Pilot Car