

Alabama Department of Transportation
Proposal Item Summary

026. STPMN-2619(256) & STPMN-2619(261)

ELMORE COUNTY

Contract Time: 30 Working Days

for constructing the Resurfacing (Micro-Surfacing Seal Coat) and Traffic Stripe on CR-23 (Coosada Road) from the junction of SR-143 in Millbrook to the junction of Blackwell Drive in Coosada (Site 1) and on CR-23 (South Edgewood Drive/Edgewood Road) from the junction of CR-2 (Cobbs Ford Road) in Millbrook to the junction of SR-143 (Site 2). Length 6.497 mi.

The Bracket Estimate on this project is from \$481,287 to \$588,240.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
403B000	1,120	Ton	Micro-Surfacing Seal Coat, Type II
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 25,300.00)
701A231	14	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	12	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701B205	115	LF	Dotted, Class 2, Type A, Traffic Stripe
701C000	4	Mile	Broken Temporary Traffic Stripe
701C001	24	Mile	Solid Temporary Traffic Stripe
701D008	26	Mile	Solid Traffic Stripe Removed (Plastic)
701D015	2	Mile	Broken Traffic Stripe Removed (Plastic)
701G251	250	LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
701H011	115	LF	Dotted Traffic Stripe Removed (Plastic)
703A002	2,232	SQFT	Traffic Control Markings, Class 2, Type A
703B002	49	SQFT	Traffic Control Legends, Class 2, Type A
703C001	1,715	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Plastic)
705A030	10	Each	Pavement Markers, Class A-H, Type 2-C
705A032	176	Each	Pavement Markers, Class A-H, Type 1-B
705A037	702	Each	Pavement Markers, Class A-H, Type 2-D
740B000	361	SQFT	Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car