

**Alabama Department of Transportation  
Proposal Item Summary**

**038. ATRP2-01-2020-001**

**AUTAUGA COUNTY**

Contract Time: 40 Working Days

DBE Goal Percent: 3.00

for constructing the Additional Turn Lanes on SR-6 (US-82) at CR-47 (Golson Road) in Prattville. Length 0.369 mi.

The Bracket Estimate on this project is from \$457,446 to \$559,100.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$16.00 per set.

*The Principal Items of work are approximately as follows:*

| Item No. | Quantity Units | Description  |
|----------|----------------|--|
| 206D000  | 299 LF         | Removing Pipe  |
| 206E000  | 2 Each         | Removing Headwalls   |
| 210A000  | 998 CUYD       | Unclassified Excavation  |
| 210D021  | 590 CUYD       | Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)   |
| 212A000  | 39 STA         | Machine Grading Shoulders  |
| 305B077  | 941 Ton        | Crushed Aggregate, Section 825, For Miscellaneous Use  |
| 401A000  | 2,870 SQYD     | Bituminous Treatment A   |
| 405A000  | 785 Gal        | Tack Coat  |
| 407B000  | 1 Mile         | Joint Sealant For Hot Mix Asphalt Pavement   |
| 408A052  | 6,310 SQYD     | Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)  |
| 424A360  | 785 Ton        | Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D           |
| 424A369  | 80 Ton         | Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D |
| 424B650  | 270 Ton        | Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D              |
| 424B657  | 50 Ton         | Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D    |
| 424B681  | 750 Ton        | Superpave Bituminous Concrete Lower Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D                |
| 428A001  | 1 Mile         | Scoring Bituminous Pavement Surface  |
| 535A001  | 108 LF         | 18" Side Drain Pipe  |
| 535A003  | 232 LF         | 30" Side Drain Pipe  |
| 600A000  | 1 LS           | Mobilization   |
| 619A101  | 6 Each         | 18" Side Drain Pipe End Treatment, Class 1   |
| 619A103  | 8 Each         | 30" Side Drain Pipe End Treatment, Class 1   |
| 650A000  | 255 CUYD       | Topsoil  |
| 652A100  | 2 Acre         | Seeding  |
| 656A010  | 2 Acre         | Mulching   |
| 659C002  | 100 SQYD       | Erosion Control Product, Type S2   |
| 665A000  | 2 Acre         | Temporary Seeding  |
| 665B001  | 6 Ton          | Temporary Mulching   |
| 665J002  | 1,950 LF       | Silt Fence   |
| 665N000  | 100 Ton        | Temporary Coarse Aggregate,ALDOT Number 1  |
| 665O001  | 1,950 LF       | Silt Fence Removal   |
| 665Q002  | 200 LF         | Wattle   |
| 666A001  | 2 Acre         | Pest Control Treatment   |
| 680A001  | 1 LS           | Geometric Controls   |
| 698A000  | 1 LS           | Construction Fuel (Maximum Bid Limited to \$ 26,000.00)  |
| 701A227  | 1 Mile         | Solid White, Class 2, Type A Traffic Stripe (5" Wide)  |
| 701A230  | 2 Mile         | Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)   |

| <b>Item No.</b> | <b>Quantity</b> | <b>Units</b> | <b>Description</b>                               |
|-----------------|-----------------|--------------|--|
| 701B207         | 360             | LF           | Dotted, Class 2, Type A Traffic Stripe (5" Wide) |
| 701C001         | 3               | Mile         | Solid Temporary Traffic Stripe                   |
| 701D007         | 1               | Mile         | Solid Traffic Stripe Removed (Paint)             |
| 701D014         | 1               | Mile         | Broken Traffic Stripe Removed (Paint)            |
| 703A002         | 1,127           | SQFT         | Traffic Control Markings, Class 2, Type A        |
| 703B002         | 121             | SQFT         | Traffic Control Legends, Class 2, Type A         |
| 703D001         | 1,127           | SQFT         | Temporary Traffic Control Markings               |
| 705A030         | 50              | Each         | Pavement Markers, Class A-H, Type 2-C            |
| 705A037         | 12              | Each         | Pavement Markers, Class A-H, Type 2-D            |
| 705A038         | 80              | Each         | Pavement Markers, Class A-H, Type 2-E            |
| 740B000         | 430             | SQFT         | Construction Signs                               |
| 740D000         | 75              | Each         | Channelizing Drums                               |
| 740E000         | 50              | Each         | Cones (36 Inches High)                           |
| 740M001         | 50              | Each         | Ballast For Cone                                 |
| 740O000         | 1               | Each         | Pilot Car  |