

**Alabama Department of Transportation
Proposal Item Summary**

042. IAR-048-000-020

MARSHALL COUNTY

Contract Time: 30 Working Days

for constructing the Widening, Resurfacing, and Traffic Stripe on Buck Island Road from the junction of Gunters Landing Road to the entrance of Global Aviation Solutions north of Guntersville. Length 0.189 mi.

The Bracket Estimate on this project is from \$156,700 to \$191,522.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 1 Acre)
210A000	100	CUYD	Unclassified Excavation
405A000	230	Gal	Tack Coat
424A341	230	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B643	230	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424C345	50	Ton	Superpave Bituminous Concrete Base Layer, Patching, 1 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424C351	66	Ton	Superpave Bituminous Concrete Base Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B003	100	Ton	Aggregate Surfacing (ALDOT #57)
430B043	75	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
610C000	100	Ton	Loose Riprap, Class 1
610D003	100	SQYD	Filter Blanket, Geotextile
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
665F000	50	Each	Hay Bales
665J002	1,000	LF	Silt Fence
665O001	1,000	LF	Silt Fence Removal
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 9,000.00)
701C001	2	Mile	Solid Temporary Traffic Stripe
701G083	2,000	LF	Solid White, Class 2T, Type A Traffic Stripe
701G089	2,000	LF	Solid Yellow, Class 2T, Type A Traffic Stripe
703A004	140	SQFT	Traffic Control Markings, Class 2T, Type A
703B004	120	SQFT	Traffic Control Legends, Class 2T, Type A
705A032	40	Each	Pavement Markers, Class A-H, Type 1-B
705A037	10	Each	Pavement Markers, Class A-H, Type 2-D
740B000	228	SQFT	Construction Signs
740O000	1	Each	Pilot Car