

**Alabama Department of Transportation  
Proposal Item Summary**

**020. RASTPAA-2319(252)**

**DALE COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 5.00

for constructing the Resurfacing and Traffic Stripe on CR-21 from the junction of SR-123 to the South Ozark City Limits (Site 1); on CR-82 from the Coffee County Line to the junction of SR-53 (US-231) (Site 2); and the Widening, Resurfacing, and Traffic Stripe on CR-33 from the junction of CR-20 to the intersection of CR-54 (Site 3). Length 3.240 mi.

The Bracket Estimate on this project is from \$573,902 to \$701,436.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C010	28	SQYD	Removing Concrete Driveway
209A000	6	Each	Mailbox Reset, Single
210D021	1,270	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
212A000	340	STA	Machine Grading Shoulders
401A006	42,779	SQYD	Bituminous Treatment G
405A000	600	Gal	Tack Coat
407B000	4	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	490	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A341	3,604	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	250	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	250	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B648	325	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B700	156	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range A/B
600A000	1	LS	Mobilization
652A100	7	Acre	Seeding
652C000	7	Acre	Mowing
656A010	7	Acre	Mulching
665F000	50	Each	Hay Bales
665J002	1,050	LF	Silt Fence
665O001	1,050	LF	Silt Fence Removal
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 30,800.00)
701A231	7	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	5	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	5	Mile	Broken Temporary Traffic Stripe
701C001	9	Mile	Solid Temporary Traffic Stripe
703A002	118	SQFT	Traffic Control Markings, Class 2, Type A
703D001	118	SQFT	Temporary Traffic Control Markings
705A032	107	Each	Pavement Markers, Class A-H, Type 1-B
705A037	310	Each	Pavement Markers, Class A-H, Type 2-D
740B000	791	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car

