

**Alabama Department of Transportation  
Proposal Item Summary**

**028. NH-0006(581)**

**MONTGOMERY COUNTY**

Contract Time: 90 Working Days

DBE Goal Percent: 6.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-6 (US-82) from the intersection of Davenport Drive to the junction of SR-53 (US-231/Troy Highway) in Montgomery. Length 4.554 mi.

The Bracket Estimate on this project is from \$2,928,550 to \$3,579,339.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206D001	3,575	LF	Removing Guardrail
206E008	20	Each	Removing Guardrail End Anchor (All Type)
305B077	500	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	14,984	Gal	Tack Coat
407B000	19	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	212,042	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
408B000	19,608	SQYD	Micro-Milling Existing Pavement (Approximately 0.00" Thru 1.00" Thick)
410H000	1	Each	Material Remixing Device
423A003	16,954	Ton	Stone Matrix Asphalt Wearing Layer, 1/2" Maximum Aggregate Size
424A356	1,022	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	1,526	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	12	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
610D003	300	SQYD	Filter Blanket, Geotextile
622A002	36	Each	Manhole Covers Reset (Sanitary)
630A001	3,475	LF	Steel Beam Guardrail, Class A, Type 2
630C001	6	Each	Guardrail End Anchor, Type 8
630C003	6	Each	Guardrail End Anchor, Type 13
630C080	8	Each	Guardrail End Anchor, Type 20 Series (MASH)
641S500	48	Each	Valve Box Reset
665G000	100	Each	Sand Bags
665J002	250	LF	Silt Fence
665O001	250	LF	Silt Fence Removal
665Q002	250	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 157,800.00)
701A108	1	Mile	Broken Black, Class W, Type B Traffic Stripe (5" Wide)
701A227	17	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	10	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	10	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	14,865	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	22	Mile	Broken Temporary Traffic Stripe
701C001	52	Mile	Solid Temporary Traffic Stripe
701G142	922	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)

Item No.	Quantity	Units	Description
701G146	953	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	488	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	1,441	LF	Solid Traffic Stripe Removed (Plastic)
701H006	922	LF	Broken Traffic Stripe Removed (Plastic)
703A002	8,375	SQFT	Traffic Control Markings, Class 2, Type A
703A011	48	SQFT	Traffic Control Markings, Class W, Type A
703B002	3,474	SQFT	Traffic Control Legends, Class 2, Type A
703C001	48	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Plastic)
703D001	16,653	SQFT	Temporary Traffic Control Markings
705A030	1,884	Each	Pavement Markers, Class A-H, Type 2-C
705A037	91	Each	Pavement Markers, Class A-H, Type 2-D
740B000	4,439	SQFT	Construction Signs
740C000	24	SQFT	Special Construction Signs
740D000	100	Each	Channelizing Drums
740E000	350	Each	Cones (36 Inches High)
740M001	350	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
745A000	500	HOUR	Uniformed Police Officer