

**Alabama Department of Transportation  
Proposal Item Summary**

**029. NH-0012(570)**

**COVINGTON COUNTY**

Contract Time: 55 Working Days

DBE Goal Percent: 1.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-12 (US-84) from the junction of CR-77 to the junction of SR-9 (US-331) in Opp. Length 3.519 mi.

The Bracket Estimate on this project is from \$1,876,861 to \$2,293,941.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
210A000	197	CUYD	Unclassified Excavation
230A000	10	RBST	Roadbed Processing
301A025	561	SQYD	Crushed Aggregate Base Course, Type B, Road Mixed, 6" Compacted Thickness
401A000	561	SQYD	Bituminous Treatment A
405A000	14,672	Gal	Tack Coat
407B000	21	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	130,393	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A361	10,383	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	375	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B651	75	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B681	75	Ton	Superpave Bituminous Concrete Lower Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	150	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
432A000	38,743	SQYD	High Density Mineral Bond
600A000	1	LS	Mobilization
614A000	58	CUYD	Slope Paving
623B000	1,433	LF	Concrete Curb, Type N
623B001	60	LF	Concrete Curb, Type N Special
654A001	552	SQYD	Solid Sodding (Bermuda)
665E000	700	SQYD	Polyethylene
665G000	200	Each	Sand Bags
665P005	2	Each	Inlet Protection, Stage 3 Or 4
665Q002	200	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 100,500.00)
701A227	9	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	8	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	8	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	9,242	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	8	Mile	Broken Temporary Traffic Stripe
701C001	57	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)

Item No.	Quantity	Units	Description
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
701G142	420	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	420	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	420	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
703A002	12,637	SQFT	Traffic Control Markings, Class 2, Type A
703B002	1,099	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,330	SQFT	Temporary Traffic Control Markings
705A030	1,105	Each	Pavement Markers, Class A-H, Type 2-C
728A000	1	Each	Truck Mounted Impact Attenuator Unit
730H001	4,100	LF	Loop Wire
740B000	1,991	SQFT	Construction Signs
740C000	9	SQFT	Special Construction Signs
740D000	100	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2