

**Alabama Department of Transportation  
Proposal Item Summary**

**030. NH-0012(574)**

**CHOCTAW COUNTY**

Contract Time: 35 Working Days

DBE Goal Percent: 2.00

for constructing the Micro-Milling, Resurfacing (Scrub Seal), Guardrail Reset, and Traffic Stripe on SR-12 (US-84) from 1.600 miles east of the junction of CR-6 (Bladon Road West) to the east end of the Jim Folsom Bridge (MP 22.723) west of Coffeerville. Length 6.601 mi.

The Bracket Estimate on this project is from \$1,536,676 to \$1,878,159.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
405A000	11,545	Gal	Tack Coat
407B000	7	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B000	116,842	SQYD	Micro-Milling Existing Pavement (Approximately 0.00" Thru 1.00" Thick)
410H000	1	Each	Material Remixing Device
424A361	9,813	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	240	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	125	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B658	125	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	13	Mile	Scoring Bituminous Pavement Surface
430B043	100	Ton	Aggregate Surfacing (1" Down, Crusher Run)
433A000	93,793	SQYD	Scrub Seal
600A000	1	LS	Mobilization
631C010	213	LF	Guardrail Reset
650A000	100	CUYD	Topsoil
652A100	3	Acre	Seeding
652C000	22	Acre	Mowing
656A010	3	Acre	Mulching
665Q002	300	LF	Wattle
666A001	3	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 90,000.00)
701A091	1	Mile	Solid White, Class W, Type A Traffic Stripe (5" Wide)
701A099	1	Mile	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701A227	13	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	5	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	6	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	18	Mile	Broken Temporary Traffic Stripe
701C001	53	Mile	Solid Temporary Traffic Stripe
701D009	2	Mile	Solid Traffic Stripe Removed (Tape)
701G150	1,380	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H007	1,380	LF	Broken Traffic Stripe Removed (Tape)
703A002	300	SQFT	Traffic Control Markings, Class 2, Type A
703D001	300	SQFT	Temporary Traffic Control Markings
705A030	119	Each	Pavement Markers, Class A-H, Type 2-C

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
705A032	141	Each	Pavement Markers, Class A-H, Type 1-B
705A037	524	Each	Pavement Markers, Class A-H, Type 2-D
740B000	894	SQFT	Construction Signs
740D000	25	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car