

**Alabama Department of Transportation
Proposal Item Summary**

031. NH-0013(616)

CLARKE COUNTY

Contract Time: 75 Working Days

DBE Goal Percent: 1.00

for constructing the Planing, Resurfacing, Guardrail Installation, and Traffic Stripe on SR-13 (US-43) from north of the junction of Calvary Road and Grant Road to north of the junction of the Bassetts Creek Bridge (MP 87.726) north of Fulton. Length 5.845 mi.

The Bracket Estimate on this project is from \$2,803,358 to \$3,426,326.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	88	LF	Removing Guardrail
206E008	9	Each	Removing Guardrail End Anchor (All Type)
209A000	1	Each	Mailbox Reset, Single
405A000	28,000	Gal	Tack Coat
407B000	13	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	276,450	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A281	14,456	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range E
424A361	7,288	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	1,292	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	1,231	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B658	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	24	Mile	Scoring Bituminous Pavement Surface
430B043	50	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630C080	9	Each	Guardrail End Anchor, Type 20 Series (MASH)
631C010	4,350	LF	Guardrail Reset
631E001	8	Each	Guardrail End Anchor, Type 8, Reset
631E003	6	Each	Guardrail End Anchor, Type 13, Reset
650A000	430	CUYD	Topsoil
652A100	14	Acre	Seeding
656A010	14	Acre	Mulching
665J002	100	LF	Silt Fence
665O001	100	LF	Silt Fence Removal
665Q002	500	LF	Wattle
666A001	14	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 149,500.00)
701A227	14	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	13	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	12	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B063	1,250	LF	Dotted, Class 2, Type A Traffic Stripe(Lane Drop 10" Wide)
701B207	9,226	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	29	Mile	Broken Temporary Traffic Stripe

Item No.	Quantity	Units	Description
701C001	56	Mile	Solid Temporary Traffic Stripe
701G142	600	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	600	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	600	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	1,200	LF	Solid Traffic Stripe Removed (Tape)
701H007	600	LF	Broken Traffic Stripe Removed (Tape)
703A002	7,086	SQFT	Traffic Control Markings, Class 2, Type A
703B002	864	SQFT	Traffic Control Legends, Class 2, Type A
703D001	504	SQFT	Temporary Traffic Control Markings
705A030	817	Each	Pavement Markers, Class A-H, Type 2-C
705A031	725	Each	Pavement Markers, Class A-H, Type 1-A
705A037	12	Each	Pavement Markers, Class A-H, Type 2-D
730H001	700	LF	Loop Wire
731A010	1	Each	Traffic Counting Units, Type K
740B000	2,700	SQFT	Construction Signs
740D000	200	Each	Channelizing Drums
740E000	250	Each	Cones (36 Inches High)
740M001	250	Each	Ballast For Cone
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit