

**Alabama Department of Transportation
Proposal Item Summary**

033. NH-HSIP-0016(529)

MOBILE COUNTY

Contract Time: 40 Working Days

DBE Goal Percent: 5.00

for constructing the Planing, Resurfacing, Guardrail Steel Blockout Replacement, Curb & Gutter Installation, Sidewalk Installation, and Traffic Stripe on SR-16 (US-90) from the junction of Lawrence Street to the junction of Water Street and Telegraph Road in Allenville. Length 0.670 mi.

The Bracket Estimate on this project is from \$516,796 to \$631,639.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$10.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C000	45	SQYD	Removing Concrete Sidewalk
206D003	128	LF	Removing Curb And Gutter
206E008	6	Each	Removing Guardrail End Anchor (All Type)
210D022	24	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A-2-4(0) or A-4(0))
212A000	49	STA	Machine Grading Shoulders
405A000	3,354	Gal	Tack Coat
407B000	4	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	33,542	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	2,768	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
618A000	42	SQYD	Concrete Sidewalk, 4" Thick
618C000	40	SQFT	Truncated Dome Retrofit
623C000	24	LF	Combination Curb & Gutter, Type C
630C079	3	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	3	Each	Guardrail End Anchor, Type 20 Series (MASH)
631C010	246	LF	Guardrail Reset
650A000	100	CUYD	Topsoil
652A100	1	Acre	Seeding
652C000	1	Acre	Mowing
654A001	210	SQYD	Solid Sodding (Bermuda)
656A010	1	Acre	Mulching
665J002	2,000	LF	Silt Fence
665O001	2,000	LF	Silt Fence Removal
665Q002	400	LF	Wattle
666A001	1	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 28,000.00)
701A227	2	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	3	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	2	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	465	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	4	Mile	Broken Temporary Traffic Stripe
701C001	6	Mile	Solid Temporary Traffic Stripe
703A002	3,210	SQFT	Traffic Control Markings, Class 2, Type A
703B002	614	SQFT	Traffic Control Legends, Class 2, Type A
703D002	1,206	SQFT	Temporary Traffic Control Markings (Paint)

Item No.	Quantity	Units	Description
703E002	399	SQFT	Temporary Traffic Control Legends (Paint)
703H000	2,867	SQFT	Specialty Traffic Control Markings
705A030	279	Each	Pavement Markers, Class A-H, Type 2-C
705A031	39	Each	Pavement Markers, Class A-H, Type 1-A
705A032	100	Each	Pavement Markers, Class A-H, Type 1-B
740B000	1,296	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit