

**Alabama Department of Transportation
Proposal Item Summary**

035. NH-0074(546)

ETOWAH COUNTY

Contract Time: 80 Working Days

DBE Goal Percent: 4.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-74 (US-278) from the junction of SR-1 (US-431) to east of the junction of Alford Bend Road in Hokes Bluff. Length 6.269 mi.

The Bracket Estimate on this project is from \$3,631,983 to \$4,439,090.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206E008	4	Each	Removing Guardrail End Anchor (All Type)
405A000	25,028	Gal	Tack Coat
407B000	14	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B001	301,458	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	23,865	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	1,803	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424C364	1,000	Ton	Superpave Bituminous Concrete Base Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424C370	277	Ton	Superpave Bituminous Concrete Base Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
430B043	20,068	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630C001	2	Each	Guardrail End Anchor, Type 8
630C080	2	Each	Guardrail End Anchor, Type 20 Series (MASH)
631C010	640	LF	Guardrail Reset
665Q002	200	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 194,000.00)
701A227	18	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	13	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	13	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B063	1,250	LF	Dotted, Class 2, Type A Traffic Stripe(Lane Drop 10" Wide)
701B207	18,700	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	15	Mile	Broken Temporary Traffic Stripe
701C001	30	Mile	Solid Temporary Traffic Stripe
701G142	1,278	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	1,278	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	1,278	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	2,556	LF	Solid Traffic Stripe Removed (Tape)
701H007	1,278	LF	Broken Traffic Stripe Removed (Tape)
703A002	13,276	SQFT	Traffic Control Markings, Class 2, Type A
703B002	1,502	SQFT	Traffic Control Legends, Class 2, Type A
703D001	33	SQFT	Temporary Traffic Control Markings
705A030	1,542	Each	Pavement Markers, Class A-H, Type 2-C
705A032	330	Each	Pavement Markers, Class A-H, Type 1-B
705A037	256	Each	Pavement Markers, Class A-H, Type 2-D
705A038	745	Each	Pavement Markers, Class A-H, Type 2-E

Item No.	Quantity	Units	Description
730H001	2,340	LF	Loop Wire
730I001	530	LF	Loop Detector Lead-In-Cable
730K000	3	Each	Traffic Signal Junction Box
730L005	370	LF	2", Non-Metallic, Conduit
740B000	1,752	SQFT	Construction Signs
740C000	42	SQFT	Special Construction Signs
740D000	200	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit