

**Alabama Department of Transportation
Proposal Item Summary**

060. STPAA-FMGR-0219(507)

DALLAS COUNTY

Contract Time: 70 Working Days

DBE Goal Percent: 2.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-219 from the junction of SR-22 southwest of Selma to the Perry County Line. Length 9.887 mi.

The Bracket Estimate on this project is from \$2,050,268 to \$2,505,883.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	100	LF	Removing Guardrail
206E008	64	Each	Removing Guardrail End Anchor (All Type)
401B101	159,035	SQYD	Bituminous Treatment F (With Polymer Additive)
405A000	4,000	Gal	Tack Coat
407B000	10	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	86,000	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A356	4,580	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424A359	225	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424A360	6,380	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	258	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	10	Mile	Scoring Bituminous Pavement Surface
430B043	1,900	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
610D003	300	SQYD	Filter Blanket, Geotextile
629D003	8	Each	Bridge Guardrail Retrofit, Type SC
630A001	400	LF	Steel Beam Guardrail, Class A, Type 2
630C003	24	Each	Guardrail End Anchor, Type 13
630C079	8	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	32	Each	Guardrail End Anchor, Type 20 Series (MASH)
665G000	100	Each	Sand Bags
665J002	250	LF	Silt Fence
665O001	250	LF	Silt Fence Removal
665Q002	250	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 121,000.00)
701A227	21	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	12	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	7	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	13	Mile	Broken Temporary Traffic Stripe
701C001	94	Mile	Solid Temporary Traffic Stripe
701G146	1,276	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	1,276	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G251	300	LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)

Item No.	Quantity	Units	Description
701H001	2,552	LF	Solid Traffic Stripe Removed (Plastic)
703A002	1,565	SQFT	Traffic Control Markings, Class 2, Type A
703B002	385	SQFT	Traffic Control Legends, Class 2, Type A
703D001	6,945	SQFT	Temporary Traffic Control Markings
703E001	770	SQFT	Temporary Traffic Control Legends
705A032	300	Each	Pavement Markers, Class A-H, Type 1-B
705A037	725	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,480	SQFT	Construction Signs
740C000	48	SQFT	Special Construction Signs
740D000	100	Each	Channelizing Drums
740E000	450	Each	Cones (36 Inches High)
740M001	450	Each	Ballast For Cone
740O000	1	Each	Pilot Car