

**Alabama Department of Transportation  
Proposal Item Summary**

**007. HSIP-2616(250)**

**ELMORE COUNTY**

Contract Time: 110 Working Days

DBE Goal Percent: 7.00

for constructing the Roundabout Installation on CR-8 (Redland Road) at the intersection of CR-59 (Firetower Road/Dozier Road) southeast of Wetumpka. Length 0.163 mi.

The Bracket Estimate on this project is from \$1,059,902 to \$1,295,435.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$19.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 8,000.00 Per Acre) (Approximately 3 Acres)
206C010	40	SQYD	Removing Concrete Driveway
206D000	263	LF	Removing Pipe
206E000	3	Each	Removing Headwalls
206E001	2	Each	Removing Inlets
209A000	1	Each	Mailbox Reset, Single
210A000	2,139	CUYD	Unclassified Excavation
210D021	1,468	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
214A000	741	CUYD	Structure Excavation
214B001	192	CUYD	Foundation Backfill, Commercial
301A012	5,751	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
305B077	50	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
401A000	4,410	SQYD	Bituminous Treatment A
405A000	300	Gal	Tack Coat
407B000	3	Mile	Joint Sealant For Hot Mix Asphalt Pavement
410H000	1	Each	Material Remixing Device
424A360	611	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B651	625	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B654	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B658	964	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B681	599	Ton	Superpave Bituminous Concrete Lower Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
530A001	482	LF	18" Roadway Pipe (Class 3 R.C.)
530A002	28	LF	24" Roadway Pipe (Class 3 R.C.)
530B003	48	LF	36" Span, 23" Rise Roadway Pipe (Class 3 R.C.)
533A098	48	LF	18" Storm Sewer Pipe (Class 3 R.C.)
533A099	42	LF	24" Storm Sewer Pipe (Class 3 R.C.)
533A348	4	LF	18" Storm Sewer Pipe (Class 3 R.C.) (Extension)
533B100	57	LF	36" Span, 23" Rise Storm Sewer Pipe (Class 3 R.C.)
534E001	157	LF	Cleaning Existing Pipe (Less Than Or Equal To 48" Horizontal Opening)
535A078	22	LF	15" Side Drain Pipe (Class 3 R.C.)
535A080	49	LF	18" Side Drain Pipe (Class 3 R.C.)
600A000	1	LS	Mobilization
602A000	15	Each	Right Of Way Markers
606A000	200	LF	6" Underdrain Pipe
610A004	26	SQYD	Loose Riprap, Class 2, 24" Thick

Item No.	Quantity	Units	Description
610D003	155	SQYD	Filter Blanket, Geotextile
614A000	227	CUYD	Slope Paving
618B003	107	SQYD	Concrete Driveway, 6" Thick (Includes Wire Mesh)
619A003	1	Each	24" Roadway Pipe End Treatment, Class 1
619A126	2	Each	18" Side Drain Pipe End Treatment, Class 2
619B068	2	Each	36" Span, 23" Rise Roadway Pipe End Treatment, Class 2
620A000	1	CUYD	Minor Structure Concrete
621A011	2	Each	Junction Boxes, Type 1 Or 1P
621C001	2	Each	Inlets, Type B
621C015	5	Each	Inlets, Type S1 Or S3 (1 Wing)
621C016	2	Each	Inlets, Type S2 Or S4 (1 Wing)
621C017	3	Each	Inlets, Type S1 Or S3 (2 Wing)
621C027	1	Each	Inlets, Type C
621C083	4	Each	Inlets, Type B (Modified) (Double)
621D002	1	Each	Inlet Units, Type C
621D015	2	Each	Inlet Units, Type S1 Or S3
621D016	2	Each	Inlet Units, Type S2 Or S4
623A007	312	LF	Concrete Gutter (Type Special)
623B000	35	LF	Concrete Curb, Type N
623B001	200	LF	Concrete Curb, Type N Special
623B002	157	LF	Concrete Curb, Type A
623C003	1,923	LF	Combination Curb & Gutter, Type C (Modified)
650A000	466	CUYD	Topsoil
652A100	3	Acre	Seeding
652C000	3	Acre	Mowing
654A000	1,278	SQYD	Solid Sodding
665A000	3	Acre	Temporary Seeding
665B001	9	Ton	Temporary Mulching
665J002	1,827	LF	Silt Fence
665O001	1,827	LF	Silt Fence Removal
665P005	17	Each	Inlet Protection, Stage 3 Or 4
665Q002	160	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 55,000.00)
701B205	352	LF	Dotted, Class 2, Type A, Traffic Stripe
701C001	3	Mile	Solid Temporary Traffic Stripe
701D005	3	Mile	Solid Traffic Stripe Removed
701G249	3,817	LF	Solid White, Class 2, Type A Traffic Stripe
701G263	4,333	LF	Solid Yellow, Class 2, Type A Traffic Stripe
703A002	750	SQFT	Traffic Control Markings, Class 2, Type A
703B002	99	SQFT	Traffic Control Legends, Class 2, Type A
703D001	102	SQFT	Temporary Traffic Control Markings
705A031	55	Each	Pavement Markers, Class A-H, Type 1-A
705A032	331	Each	Pavement Markers, Class A-H, Type 1-B
705A037	8	Each	Pavement Markers, Class A-H, Type 2-D
705A038	96	Each	Pavement Markers, Class A-H, Type 2-E
740B000	673	SQFT	Construction Signs
740D000	150	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740F002	5	Each	Barricades, Type III
740M001	50	Each	Ballast For Cone
742A001	4	Each	Portable Changeable Message Sign, Type 2
745A000	150	HOUR	Uniformed Police Officer