

**Alabama Department of Transportation
Proposal Item Summary**

012. IM-HSIP-I059(411)

ST. AND CLAIR COUNTIES

Contract Time: 5/31/2021 Completion Date

DBE Goal Percent: 1.00

for constructing the Pavement Rehabilitation (Micro-Milling, Resurfacing, Guardrail Replacement, and Traffic Stripe) on I-59 from the Jefferson County Line to north of the SR-23 Overpass southeast of Springville. Length 8.655 mi.

The Bracket Estimate on this project is from \$15,239,603 to \$18,626,182.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C025	1,816	SQYD	Removing Bituminous Pavement On Concrete Surfaces
206D001	225	LF	Removing Guardrail
206E008	14	Each	Removing Guardrail End Anchor (All Type)
210A000	22,354	CUYD	Unclassified Excavation
210D001	700	CUYD	Borrow Excavation (Loose Truckbed Measurement)
331A012	160,943	SQYD	Roller Compacted Concrete, 5.0 inches Thick
408B000	284,463	SQYD	Micro-Milling Existing Pavement (Approximately 0.00" Thru 1.00" Thick)
410H000	1	Each	Material Remixing Device
420A015	15,747	Ton	Polymer Modified Open Graded Friction Course
420B000	51,531	Gal	Open Graded Friction Course Tack Coat
453C000	9,884	SQYD	Removal Of Concrete Pavement Slab
453D000	2,746	CUYD	Concrete Pavement Replacement Slab
454A002	208,000	LF	Cleaning And Sealing Concrete Pavement, Type II, Joints
454A003	11,000	LF	Cleaning And Sealing Concrete Pavement, Type II, Cracks
454A007	193,862	LF	Cleaning And Sealing Concrete Pavement, Type II, Joints (Longitudinal Shoulder Joints)
455A000	252,079	SQYD	Grinding Concrete Pavement
455C000	1	Each	Smoothness Testing, Certified Inertial Profiler
460A000	8,000	LB	Patching
534A000	605	Each	Cleaning Pipe Underdrain Outlets
600A000	1	LS	Mobilization
603A001	1	Each	Furnishing Type 2 Field Office
630A001	150	LF	Steel Beam Guardrail, Class A, Type 2
630A034	200	LF	Steel Beam Guardrail, Class A, Type 2 (8'-0" Post)
630C001	13	Each	Guardrail End Anchor, Type 8
630C079	1	Each	Guardrail End Anchor, Type 13 (MASH)
631C010	15,147	LF	Guardrail Reset
650A000	280	CUYD	Topsoil
652A100	3	Acre	Seeding
654A001	1,050	SQYD	Solid Sodding (Bermuda)
656A010	3	Acre	Mulching
665A000	3	Acre	Temporary Seeding
665B001	9	Ton	Temporary Mulching
665G000	500	Each	Sand Bags
665J002	2,000	LF	Silt Fence
665N000	200	Ton	Temporary Coarse Aggregate,ALDOT Number 1
665O001	2,000	LF	Silt Fence Removal
665P005	40	Each	Inlet Protection, Stage 3 Or 4
665Q002	1,000	LF	Wattle
666A001	3	Acre	Pest Control Treatment

Item No.	Quantity	Units	Description
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 850,000.00)
701A227	19	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	19	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	18	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	3,608	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	52	Mile	Broken Temporary Traffic Stripe
701C001	114	Mile	Solid Temporary Traffic Stripe
703A002	4,155	SQFT	Traffic Control Markings, Class 2, Type A
703B002	164	SQFT	Traffic Control Legends, Class 2, Type A
705A011	555	Each	Pavement Markers, Class C, Type 1-A
705A012	216	Each	Pavement Markers, Class C, Type 1-B
705A022	1,447	Each	Pavement Markers, Class C, Type 2-C
705A030	1,447	Each	Pavement Markers, Class A-H, Type 2-C
705A031	555	Each	Pavement Markers, Class A-H, Type 1-A
705A032	216	Each	Pavement Markers, Class A-H, Type 1-B
730H001	800	LF	Loop Wire
731A001	2	Each	Traffic Counting Units, Type B
731B000	1	Each	Pole for Mounting Traffic Detection Equipment
740B000	3,946	SQFT	Construction Signs
740C000	72	SQFT	Special Construction Signs
740D000	650	Each	Channelizing Drums
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2
999 000	1,400	HOUR	Trainee Hours At 80 Cents Per Hour