

**Alabama Department of Transportation
Proposal Item Summary**

015. IM-I010(348)

MOBILE COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 1.00

for constructing the Planing, Resurfacing, and Traffic Stripe on I-10 through the Wallace Tunnel in Mobile. Length 0.887 mi.

The Bracket Estimate on this project is from \$1,302,003 to \$1,591,337.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206E008	6	Each	Removing Guardrail End Anchor (All Type)
206E043	116	Each	Removing Raised Pavement Markers
405A000	2,867	Gal	Tack Coat
407B000	2	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	28,661	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
423A003	3,153	Ton	Stone Matrix Asphalt Wearing Layer, 1/2" Maximum Aggregate Size
431B001	28,338	SQYD	High Friction Surface Treatment
490A000	247	SQYD	Blast Cleaning
534D000	6	Each	Cleaning Existing Drop Inlet
600A000	1	LS	Mobilization
630A001	88	LF	Steel Beam Guardrail, Class A, Type 2
630C079	3	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	3	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	250	CUYD	Topsoil
654A001	270	SQYD	Solid Sodding (Bermuda)
665J002	50	LF	Silt Fence
665O001	50	LF	Silt Fence Removal
665Q002	50	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 69,000.00)
701A227	2	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	2	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	2	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	921	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	7	Mile	Broken Temporary Traffic Stripe
701C001	15	Mile	Solid Temporary Traffic Stripe
701G142	53	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	136	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	53	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	189	LF	Solid Traffic Stripe Removed (Tape)
701H007	53	LF	Broken Traffic Stripe Removed (Tape)
703A002	1,608	SQFT	Traffic Control Markings, Class 2, Type A
703A011	194	SQFT	Traffic Control Markings, Class W, Type A
703C003	194	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Tape)
705A022	116	Each	Pavement Markers, Class C, Type 2-C
705A030	1,319	Each	Pavement Markers, Class A-H, Type 2-C
705A032	24	Each	Pavement Markers, Class A-H, Type 1-B
730H001	750	LF	Loop Wire
730I001	100	LF	Loop Detector Lead-In-Cable

Item No.	Quantity	Units	Description
740B000	931	SQFT	Construction Signs
740C000	23	SQFT	Special Construction Signs
740D000	150	Each	Channelizing Drums
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2