

**Alabama Department of Transportation  
Proposal Item Summary**

**018. IM-I565(316)**

**MADISON COUNTY**

Contract Time: 250 Working Days

DBE Goal Percent: 5.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on I-565 from 0.280 mile east of the Intergraph Way Underpass (MP 10.100) to 0.260 mile east of the Triana Boulevard Overpass (MP 18.322) in Huntsville. Length 8.231 mi.

The Bracket Estimate on this project is from \$14,249,080 to \$17,415,543.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$15.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
405A000	57,360	Gal	Tack Coat
407B000	61	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B000	513,597	SQYD	Micro-Milling Existing Pavement (Approximately 0.00" Thru 1.00" Thick)
408B001	941,740	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
420A015	28,248	Ton	Polymer Modified Open Graded Friction Course
420B000	92,448	Gal	Open Graded Friction Course Tack Coat
423A003	53,928	Ton	Stone Matrix Asphalt Wearing Layer, 1/2" Maximum Aggregate Size
424A360	39,967	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B285	1,000	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range E
428A001	33	Mile	Scoring Bituminous Pavement Surface
430B043	12,011	Ton	Aggregate Surfacing (1" Down, Crusher Run)
534A000	145	Each	Cleaning Pipe Underdrain Outlets
600A000	1	LS	Mobilization
610D003	150	SQYD	Filter Blanket, Geotextile
631C010	21,005	LF	Guardrail Reset
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
665A000	1	Acre	Temporary Seeding
665B001	3	Ton	Temporary Mulching
665Q002	500	LF	Wattle
666A001	1	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 760,260.00)
701A227	28	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	27	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	50	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B027	1,670	LF	Dotted, Class W, Type A Traffic Stripe (5" Wide)
701B059	365	LF	Dotted, Class W, Type A Traffic Stripe(Lane Drop 10" Wide)
701B063	26,600	LF	Dotted, Class 2, Type A Traffic Stripe(Lane Drop 10" Wide)
701B207	23,596	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	200	Mile	Broken Temporary Traffic Stripe
701C001	186	Mile	Solid Temporary Traffic Stripe
701F000	94,384	LF	Dotted Temporary Traffic Stripe
701F010	106,400	LF	Dotted Temporary Traffic Stripe (Lane Drop)
701G142	7,251	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	5,884	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	5,884	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	11,767	LF	Solid Traffic Stripe Removed (Tape)

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
701H007	7,251	LF	Broken Traffic Stripe Removed (Tape)
703A002	26,717	SQFT	Traffic Control Markings, Class 2, Type A
703A011	2,015	SQFT	Traffic Control Markings, Class W, Type A
703B002	2,054	SQFT	Traffic Control Legends, Class 2, Type A
703D001	3,024	SQFT	Temporary Traffic Control Markings
703H000	288	SQFT	Specialty Traffic Control Markings
705A030	4,442	Each	Pavement Markers, Class A-H, Type 2-C
705A031	800	Each	Pavement Markers, Class A-H, Type 1-A
705A032	378	Each	Pavement Markers, Class A-H, Type 1-B
730H001	9,900	LF	Loop Wire
730I001	750	LF	Loop Detector Lead-In-Cable
740B000	4,363	SQFT	Construction Signs
740C000	100	SQFT	Special Construction Signs
740D000	400	Each	Channelizing Drums
741C010	4	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	4	Each	Portable Changeable Message Sign, Type 2