

**Alabama Department of Transportation  
Proposal Item Summary**

**023. NH-0013(617)**

**CLARKE COUNTY**

Contract Time: 60 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-13 (US-43) from the north end of the Bassetts Creek Bridge (MP 87.690) to north of the junction of SR-5 (MP 93.120) in Thomasville. Length 5.430 mi.

The Bracket Estimate on this project is from \$2,203,785 to \$2,693,515.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity Units	Description
209A000	1 Each	Mailbox Reset, Single
405A000	23,400 Gal	Tack Coat
407B000	24 Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	233,932 SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1 Each	Material Remixing Device
424A281	16,440 Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range E
424A361	2,562 Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	1,215 Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	500 Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	100 Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	8 Mile	Scoring Bituminous Pavement Surface
430B043	100 Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1 LS	Mobilization
607D000	6,167 SQYD	Paving Geotextile
607E000	1,850 Gal	Asphalt Sealant
650A000	250 CUYD	Topsoil
652A100	7 Acre	Seeding
652C000	7 Acre	Mowing
656A010	7 Acre	Mulching
665J002	100 LF	Silt Fence
665O001	100 LF	Silt Fence Removal
665Q002	100 LF	Wattle
666A001	7 Acre	Pest Control Treatment
698A000	1 LS	Construction Fuel (Maximum Bid Limited to \$ 118,900.00)
701A227	11 Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	11 Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	11 Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	8 Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	5,719 LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	72 Mile	Broken Temporary Traffic Stripe
701C001	57 Mile	Solid Temporary Traffic Stripe
703A002	7,947 SQFT	Traffic Control Markings, Class 2, Type A
703B002	909 SQFT	Traffic Control Legends, Class 2, Type A
703D001	3,864 SQFT	Temporary Traffic Control Markings
703E001	629 SQFT	Temporary Traffic Control Legends

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
705A030	570	Each	Pavement Markers, Class A-H, Type 2-C
705A031	659	Each	Pavement Markers, Class A-H, Type 1-A
705A032	106	Each	Pavement Markers, Class A-H, Type 1-B
705A037	557	Each	Pavement Markers, Class A-H, Type 2-D
705A038	53	Each	Pavement Markers, Class A-H, Type 2-E
730H001	17,632	LF	Loop Wire
740B000	2,262	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	400	Each	Cones (36 Inches High)
740M001	400	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit