

**Alabama Department of Transportation
Proposal Item Summary**

027. NH-HSIP-0003(635)

BALDWIN COUNTY

Contract Time: 75 Working Days

DBE Goal Percent: 1.00

for constructing the Planing, Resurfacing, Steel Blockout Replacement, and Traffic Stripe on SR-3 (US-31) from a point south of the Bay Minette City Limits (MP 17.489) to the junction of West Pine Street to include Intersection Improvements at SR-59. Length 3.569 mi.

The Bracket Estimate on this project is from \$1,825,896 to \$2,231,651.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C002	27	SQYD	Removing Concrete Slope Paving
206E008	18	Each	Removing Guardrail End Anchor (All Type)
212A000	622	STA	Machine Grading Shoulders
405A000	15,622	Gal	Tack Coat
407B000	15	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	156,227	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	12,196	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	693	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B659	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B662	46	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
431B001	1,653	SQYD	High Friction Surface Treatment
490A000	680	SQYD	Blast Cleaning
490B003	680	SQYD	Bridge Deck Overlay
490D000	10	SQFT	Bridge Deck Spall Repair
600A000	1	LS	Mobilization
610D003	100	SQYD	Filter Blanket, Geotextile
614A000	5	CUYD	Slope Paving
623B000	40	LF	Concrete Curb, Type N
629D002	6	Each	Bridge Guardrail Retrofit, Type BC
630C001	5	Each	Guardrail End Anchor, Type 8
630C079	6	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	7	Each	Guardrail End Anchor, Type 20 Series (MASH)
631C010	2,803	LF	Guardrail Reset
650A000	500	CUYD	Topsoil
652A100	1	Acre	Seeding
654A001	2,138	SQYD	Solid Sodding (Bermuda)
656A010	1	Acre	Mulching
665G000	50	Each	Sand Bags
665J002	1,000	LF	Silt Fence
665O001	1,000	LF	Silt Fence Removal
665Q002	100	LF	Wattle
666A001	1	Acre	Pest Control Treatment

Item No.	Quantity	Units	Description
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 97,450.00)
701A227	8	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	7	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	7	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	12,085	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	20	Mile	Broken Temporary Traffic Stripe
701C001	39	Mile	Solid Temporary Traffic Stripe
701G146	528	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	528	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	528	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	1,056	LF	Solid Traffic Stripe Removed (Plastic)
701H006	528	LF	Broken Traffic Stripe Removed (Plastic)
703A002	7,351	SQFT	Traffic Control Markings, Class 2, Type A
703B002	1,277	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,209	SQFT	Temporary Traffic Control Markings
705A030	1,297	Each	Pavement Markers, Class A-H, Type 2-C
705A032	55	Each	Pavement Markers, Class A-H, Type 1-B
705A037	119	Each	Pavement Markers, Class A-H, Type 2-D
705A038	28	Each	Pavement Markers, Class A-H, Type 2-E
730A012	1	LS	Removal Of Existing Traffic Control Unit (Partial) (SR-3 (US-31) at SR-59)
730C000	1	LS	Furnishing And Installing Traffic Control Unit (SR-3 (US-31) at SR-59)
730H001	10,600	LF	Loop Wire
730I001	4,881	LF	Loop Detector Lead-In-Cable
730K000	3	Each	Traffic Signal Junction Box
730L002	100	LF	1", Metallic, Conduit
730L005	380	LF	2", Non-Metallic, Conduit
730R150	1	Each	Controller Unit, Type III, 8 phase
730U400	1	LS	Radar Detection System (SR-3 (US-31) at SR-59)
740B000	1,127	SQFT	Construction Signs
740D000	20	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
756A022	210	LF	4" Electrical Conduit, 1 Line, Type 5 Installation