

**Alabama Department of Transportation
Proposal Item Summary**

028. NH-HSIP-0003(638)

AUTAUGA COUNTY

Contract Time: 35 Working Days

DBE Goal Percent: 1.00

for constructing the Safety Widening, Planing, Resurfacing, and Traffic Stripe on SR-3 (US-31) from the North City Limits of Prattville to the I-65 Interchange. Length 3.714 mi.

The Bracket Estimate on this project is from \$1,030,633 to \$1,259,663.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	5,450	Gal	Tack Coat
407B000	6	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	70,600	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	6,050	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	375	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B663	1,270	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	6	Mile	Scoring Bituminous Pavement Surface
430B043	607	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
610D003	980	SQYD	Filter Blanket, Geotextile
665G000	350	Each	Sand Bags
665J002	1,050	LF	Silt Fence
665O001	1,050	LF	Silt Fence Removal
665Q002	700	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 61,000.00)
701A227	11	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	6	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	5	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,770	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	10	Mile	Broken Temporary Traffic Stripe
701C001	31	Mile	Solid Temporary Traffic Stripe
703A002	1,862	SQFT	Traffic Control Markings, Class 2, Type A
703B002	225	SQFT	Traffic Control Legends, Class 2, Type A
703D001	9,724	SQFT	Temporary Traffic Control Markings
705A030	100	Each	Pavement Markers, Class A-H, Type 2-C
705A032	600	Each	Pavement Markers, Class A-H, Type 1-B
705A037	150	Each	Pavement Markers, Class A-H, Type 2-D
705A038	100	Each	Pavement Markers, Class A-H, Type 2-E
740B000	1,178	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	350	Each	Cones (36 Inches High)
740M001	350	Each	Ballast For Cone

Item No.	Quantity	Units	Description
7400000	1 Each	Pilot Car	