

**Alabama Department of Transportation
Proposal Item Summary**

032. RASTPAA-4915(251)

MOBILE COUNTY

Contract Time: 110 Working Days

DBE Goal Percent: 2.00

for constructing the Widening, Planing, Resurfacing, and Traffic Stripe on CR-33 (Dawes Road) from the junction of Scott Dairy Loop Road South to the junction of D 'Iberville Drive West northwest of Theodore. Length 1.336 mi.

The Bracket Estimate on this project is from \$1,199,352 to \$1,465,875.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$39.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201C000	1	LS	Clearing
206C002	19	SQYD	Removing Concrete Slope Paving
206C003	28	SQYD	Removing Concrete Flumes
206C010	138	SQYD	Removing Concrete Driveway
206D000	541	LF	Removing Pipe
206E000	10	Each	Removing Headwalls
206E062	1	Each	Removing Tree (19 - 36 Inch)
206E063	1	Each	Removing Tree (37 Inch Or Larger)
209A000	59	Each	Mailbox Reset, Single
210A000	1,784	CUYD	Unclassified Excavation
210D022	2,243	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A-2-4(0) or A-4(0))
214A000	204	CUYD	Structure Excavation
214B001	116	CUYD	Foundation Backfill, Commercial
230A000	18	RBST	Roadbed Processing
301A022	1,342	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 8.5" Compacted Thickness
401A000	1,342	SQYD	Bituminous Treatment A
405A000	2,222	Gal	Tack Coat
407B000	2	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	16,427	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	1,865	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	144	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B651	3,558	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	24	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	188	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B681	190	Ton	Superpave Bituminous Concrete Lower Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B692	374	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
430B040	250	Ton	Aggregate Surfacing (Crushed Aggregate Base, Type B)
502A000	1,515	LB	Steel Reinforcement
524B011	11	CUYD	Culvert Concrete Extension (Cast In Place)
530A001	118	LF	18" Roadway Pipe (Class 3 R.C.)
530A102	35	LF	24" Roadway Pipe (Class 3 R.C.) (Extension)
530B003	79	LF	36" Span, 23" Rise Roadway Pipe (Class 3 R.C.)
535A080	501	LF	18" Side Drain Pipe (Class 3 R.C.)

Item No.	Quantity	Units	Description
535A301	20	LF	18" Side Drain Pipe (Extension)
535B088	180	LF	22" Span, 14" Rise Side Drain Pipe (Class 3 R.C.)
535B300	16	LF	18" Span, 11" Rise Side Drain Pipe (Class 3 R.C.)(Extension)
600A000	1	LS	Mobilization
610C001	148	Ton	Loose Riprap, Class 2
610D003	2,027	SQYD	Filter Blanket, Geotextile
614A000	9	CUYD	Slope Paving
619A003	4	Each	24" Roadway Pipe End Treatment, Class 1
619A101	21	Each	18" Side Drain Pipe End Treatment, Class 1
619B115	1	Each	18" Span, 11" Rise Side Drain Pipe End Treatment, Class 1
619B116	10	Each	22" Span, 14" Rise Side Drain Pipe End Treatment, Class 1
619B118	2	Each	36" Span, 23" Rise Side Drain Pipe End Treatment, Class 1
650A000	1,832	CUYD	Topsoil
652A100	4	Acre	Seeding
652C000	8	Acre	Mowing
654A001	2,641	SQYD	Solid Sodding (Bermuda)
656A010	4	Acre	Mulching
659C001	500	SQYD	Erosion Control Product, Type S3
659C005	968	SQYD	Erosion Control Product, Type C4
665A000	4	Acre	Temporary Seeding
665B001	12	Ton	Temporary Mulching
665E000	1,000	SQYD	Polyethylene
665G000	315	Each	Sand Bags
665I000	75	Ton	Temporary Riprap, Class 2
665J002	3,513	LF	Silt Fence
665N000	50	Ton	Temporary Coarse Aggregate,ALDOT Number 1
665N001	50	Ton	Temporary Coarse Aggregate,ALDOT Number 4
665O001	3,513	LF	Silt Fence Removal
665P005	4	Each	Inlet Protection, Stage 3 Or 4
665Q002	2,532	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 69,000.00)
701A227	3	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	2	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	100	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	1	Mile	Broken Temporary Traffic Stripe
701C003	12	Mile	Solid Temporary Traffic Stripe (Paint)
701F001	200	LF	Dotted Temporary Traffic Stripe (Paint)
701H000	7,504	LF	Solid Traffic Stripe Removed (Paint)
703A002	1,056	SQFT	Traffic Control Markings, Class 2, Type A
703B002	23	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,142	SQFT	Temporary Traffic Control Markings
705A023	270	Each	Pavement Markers, Class C, Type 2-D
705A030	8	Each	Pavement Markers, Class A-H, Type 2-C
705A032	189	Each	Pavement Markers, Class A-H, Type 1-B
705A037	173	Each	Pavement Markers, Class A-H, Type 2-D
705A038	117	Each	Pavement Markers, Class A-H, Type 2-E
707A027	2	Each	Type 1B, Red And Yellow Delineator Installation
711A000	1	LS	Roadway Sign Relocation
740B000	1,016	SQFT	Construction Signs
740D000	215	Each	Channelizing Drums
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car

Item No.	Quantity	Units	Description
741C010	2 Each		Portable Sequential Arrow And Chevron Sign Unit
742A001	2 Each		Portable Changeable Message Sign, Type 2