

**Alabama Department of Transportation  
Proposal Item Summary**

**037. RP-STPAA-HSIP-FMGR-0009(578)**

**CALHOUN COUNTY**

Contract Time: 90 Working Days

DBE Goal Percent: 3.00

for constructing the Micro-Milling, Resurfacing, Bridge Guardrail Retrofit, and Traffic Stripe on SR-9 from the junction of SR-4 (US-78) west of Heflin to a point 0.070 mile south of the Nature Trail (MP 230.233). Length 10.921 mi.

The Bracket Estimate on this project is from \$2,804,258 to \$3,427,427.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206D001	5,650	LF	Removing Guardrail
206E008	28	Each	Removing Guardrail End Anchor (All Type)
401B100	183,503	SQYD	Bituminous Treatment E (With Polymer Additive)
405A000	10,093	Gal	Tack Coat
407B000	12	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	27,104	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
408B001	156,399	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	17,157	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	500	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B654	700	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	350	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B658	2,534	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	21	Mile	Scoring Bituminous Pavement Surface
430B043	440	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
629D003	12	Each	Bridge Guardrail Retrofit, Type SC
630A001	5,650	LF	Steel Beam Guardrail, Class A, Type 2
630C001	4	Each	Guardrail End Anchor, Type 8
630C079	12	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	12	Each	Guardrail End Anchor, Type 20 Series (MASH)
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 165,000.00)
701A227	22	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	7	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	10	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,474	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	30	Mile	Broken Temporary Traffic Stripe
701C001	86	Mile	Solid Temporary Traffic Stripe
701G146	1,141	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	380	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	380	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	1,521	LF	Solid Traffic Stripe Removed (Tape)
701H007	380	LF	Broken Traffic Stripe Removed (Tape)
703A002	7,219	SQFT	Traffic Control Markings, Class 2, Type A

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
703B002	202	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,760	SQFT	Temporary Traffic Control Markings
705A032	510	Each	Pavement Markers, Class A-H, Type 1-B
705A037	585	Each	Pavement Markers, Class A-H, Type 2-D
705A038	130	Each	Pavement Markers, Class A-H, Type 2-E
740B000	1,720	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740O000	1	Each	Pilot Car