

**Alabama Department of Transportation
Proposal Item Summary**

040. STPAA-0003(636)

CONECUH COUNTY

Contract Time: 45 Working Days

DBE Goal Percent: 4.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-3 from the north end of the CSX Railroad Bridge (MP 95.972) in Evergreen to MP 102.000. Length 6.027 mi.

The Bracket Estimate on this project is from \$1,474,332 to \$1,801,961.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$11.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206E008	4	Each	Removing Guardrail End Anchor (All Type)
212A000	620	STA	Machine Grading Shoulders
405A000	12,402	Gal	Tack Coat
407B000	12	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	124,015	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	9,798	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	438	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	12	Mile	Scoring Bituminous Pavement Surface
534E001	56	LF	Cleaning Existing Pipe (Less Than Or Equal To 48" Horizontal Opening)
600A000	1	LS	Mobilization
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
631C010	413	LF	Guardrail Reset
650A000	1,500	CUYD	Topsoil
652A100	7	Acre	Seeding
652C000	150	Acre	Mowing
654A001	500	SQYD	Solid Sodding (Bermuda)
656A010	7	Acre	Mulching
665J002	5,000	LF	Silt Fence
665O001	5,000	LF	Silt Fence Removal
665Q002	500	LF	Wattle
666A001	7	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 79,400.00)
701A227	13	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	13	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	1	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B063	750	LF	Dotted, Class 2, Type A Traffic Stripe(Lane Drop 10" Wide)
701B207	1,688	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	6	Mile	Broken Temporary Traffic Stripe
701C001	75	Mile	Solid Temporary Traffic Stripe
703A002	5,545	SQFT	Traffic Control Markings, Class 2, Type A
703B002	450	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,854	SQFT	Temporary Traffic Control Markings

Item No.	Quantity	Units	Description
705A030	1,357	Each	Pavement Markers, Class A-H, Type 2-C
705A032	778	Each	Pavement Markers, Class A-H, Type 1-B
705A037	683	Each	Pavement Markers, Class A-H, Type 2-D
705A038	351	Each	Pavement Markers, Class A-H, Type 2-E
730H001	1,300	LF	Loop Wire
730I001	690	LF	Loop Detector Lead-In-Cable
740B000	1,672	SQFT	Construction Signs
740D000	25	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car