

**Alabama Department of Transportation  
Proposal Item Summary**

---

**043. STPAA-0145(507)**

**CHILTON COUNTY**

Contract Time: 30 Working Days

for constructing the Micro-Surfacing, Scrub Seal, and Traffic Stripe on SR-145 from the I-65 Underpass to a point south of the Waxahatchee Creek Bridge northeast of Clanton. Length 10.846 mi.

The Bracket Estimate on this project is from \$1,054,414 to \$1,288,728.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
209A000	7	Each	Mailbox Reset, Single
403B000	1,772	Ton	Micro-Surfacing Seal Coat, Type II
433A000	170,685	SQYD	Scrub Seal
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 56,260.00)
701A227	22	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	8	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	10	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	19	Mile	Broken Temporary Traffic Stripe
701C001	59	Mile	Solid Temporary Traffic Stripe
701G146	500	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	250	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	500	LF	Solid Traffic Stripe Removed (Tape)
701H007	250	LF	Broken Traffic Stripe Removed (Tape)
703A002	2,022	SQFT	Traffic Control Markings, Class 2, Type A
705A032	265	Each	Pavement Markers, Class A-H, Type 1-B
705A037	567	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,194	SQFT	Construction Signs
740E000	25	Each	Cones (36 Inches High)
740M001	25	Each	Ballast For Cone
740O000	1	Each	Pilot Car