

**Alabama Department of Transportation  
Proposal Item Summary**

**044. STPAA-0167(515)**

**GENEVA COUNTY**

Contract Time: 30 Working Days

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-167 from the Florida State Line to the junction of SR-123 south of Hartford. Length 7.086 mi.

The Bracket Estimate on this project is from \$1,145,264 to \$1,399,767.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206D001	425	LF	Removing Guardrail
206E008	16	Each	Removing Guardrail End Anchor (All Type)
209A000	5	Each	Mailbox Reset, Single
405A000	14,616	Gal	Tack Coat
407B000	8	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B000	146,161	SQYD	Micro-Milling Existing Pavement (Approximately 0.00" Thru 1.00" Thick)
410H000	1	Each	Material Remixing Device
424A356	6,578	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	101	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
428A001	15	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
630A001	150	LF	Steel Beam Guardrail, Class A, Type 2
630C080	16	Each	Guardrail End Anchor, Type 20 Series (MASH)
630G003	325	LF	Steel Beam Guardrail for Culvert, Class A, Type 2, Case 3
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 61,500.00)
701A227	15	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	6	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	4	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,280	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	12	Mile	Broken Temporary Traffic Stripe
701C001	47	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
703A002	2,048	SQFT	Traffic Control Markings, Class 2, Type A
703B002	180	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,431	SQFT	Temporary Traffic Control Markings
705A001	41	Each	Pavement Markers, Class A, Type 1-B
705A006	20	Each	Pavement Markers, Class A, Type 2-E
705A030	170	Each	Pavement Markers, Class A-H, Type 2-C
705A032	418	Each	Pavement Markers, Class A-H, Type 1-B
705A037	1,105	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,164	SQFT	Construction Signs

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
740C000	5	SQFT	Special Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car