

**Alabama Department of Transportation
Proposal Item Summary**

049. STPAA-HSIP-0041(521)

MONROE COUNTY

Contract Time: 45 Working Days

DBE Goal Percent: 2.00

for constructing the Safety Widening, Resurfacing (Scrub Seal), Guardrail Reset, and Traffic Stripe on SR-41 from the junction of CR-17 to the Wilcox County Line. Length 9.155 mi.

The Bracket Estimate on this project is from \$2,008,091 to \$2,454,334.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	150	LF	Removing Guardrail
206E008	12	Each	Removing Guardrail End Anchor (All Type)
212A000	952	STA	Machine Grading Shoulders
405A000	15,057	Gal	Tack Coat
407B000	10	Mile	Joint Sealant For Hot Mix Asphalt Pavement
410H000	1	Each	Material Remixing Device
424A340	10,377	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424A349	179	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424C350	3,701	Ton	Superpave Bituminous Concrete Base Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	19	Mile	Scoring Bituminous Pavement Surface
430B043	1,500	Ton	Aggregate Surfacing (1" Down, Crusher Run)
433A000	126,861	SQYD	Scrub Seal
600A000	1	LS	Mobilization
630C080	12	Each	Guardrail End Anchor, Type 20 Series (MASH)
631C010	2,638	LF	Guardrail Reset
631E003	8	Each	Guardrail End Anchor, Type 13, Reset
650A000	1,500	CUYD	Topsoil
652A100	11	Acre	Seeding
652C000	44	Acre	Mowing
654A000	600	SQYD	Solid Sodding
656A010	11	Acre	Mulching
665B001	33	Ton	Temporary Mulching
665J002	400	LF	Silt Fence
665O001	400	LF	Silt Fence Removal
665Q002	1,500	LF	Wattle
666A001	11	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 108,500.00)
701A227	19	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	17	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	4	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	7	Mile	Broken Temporary Traffic Stripe
701C001	69	Mile	Solid Temporary Traffic Stripe
701G146	1,020	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)

Item No.	Quantity	Units	Description
701G150	355	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	665	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	1,685	LF	Solid Traffic Stripe Removed (Tape)
701H007	355	LF	Broken Traffic Stripe Removed (Tape)
703A002	216	SQFT	Traffic Control Markings, Class 2, Type A
703D001	216	SQFT	Temporary Traffic Control Markings
705A030	1,796	Each	Pavement Markers, Class A-H, Type 2-C
705A032	200	Each	Pavement Markers, Class A-H, Type 1-B
705A037	1,110	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,788	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car