

**Alabama Department of Transportation
Proposal Item Summary**

051. STPAA-HSIP-FMGR-0175(501)

PERRY COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 1.00

for constructing the Safety Widening, Resurfacing, Guardrail Installation, and Traffic Stripe on SR-175 from the junction of SR-14 northeast of Marion to the junction of SR-5 south of Heiberger. Length 5.325 mi.

The Bracket Estimate on this project is from \$725,017 to \$886,132.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C010	28	SQYD	Removing Concrete Driveway
206D001	263	LF	Removing Guardrail
206E008	8	Each	Removing Guardrail End Anchor (All Type)
305B077	9	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	10,717	Gal	Tack Coat
407B000	6	Mile	Joint Sealant For Hot Mix Asphalt Pavement
410H000	1	Each	Material Remixing Device
424B634	719	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B677	1,623	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424T000	3,102	Ton	Superpave Bituminous Concrete Wearing Layer, Thin Lift Mix, ESAL Range A/B
600A000	1	LS	Mobilization
630A001	263	LF	Steel Beam Guardrail, Class A, Type 2
630C080	8	Each	Guardrail End Anchor, Type 20 Series (MASH)
631C010	213	LF	Guardrail Reset
665Q002	1,500	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 38,500.00)
701A227	11	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	5	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	4	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	4	Mile	Broken Temporary Traffic Stripe
701C001	27	Mile	Solid Temporary Traffic Stripe
701G146	600	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	300	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	300	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	900	LF	Solid Traffic Stripe Removed (Tape)
701H007	300	LF	Broken Traffic Stripe Removed (Tape)
703A002	934	SQFT	Traffic Control Markings, Class 2, Type A
703B002	56	SQFT	Traffic Control Legends, Class 2, Type A
703D001	76	SQFT	Temporary Traffic Control Markings
703E001	56	SQFT	Temporary Traffic Control Legends
705A032	122	Each	Pavement Markers, Class A-H, Type 1-B
705A037	336	Each	Pavement Markers, Class A-H, Type 2-D
740B000	767	SQFT	Construction Signs
740C000	36	SQFT	Special Construction Signs
740D000	10	Each	Channelizing Drums
740E000	25	Each	Cones (36 Inches High)
740M001	25	Each	Ballast For Cone
740O000	1	Each	Pilot Car