

**Alabama Department of Transportation  
Proposal Item Summary**

---

**060. STPOA-0820(250)**

**CALHOUN COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 1.00

for constructing the Planing, Resurfacing, and Traffic Stripe on Whites Gap Road Southeast from the junction of SR-21 to the southeast Jacksonville City Limits (Site 1) and on Whites Gap Road from the junction of Cottaquilla Road to the junction of SR-9 (Site 2). Length 4.765 mi.

The Bracket Estimate on this project is from \$877,489 to \$1,072,478.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$2.00 per set.

*The Principal Items of work are approximately as follows:*

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
401A013	16,528	SQYD	Bituminous Treatment JG
401B108	60,195	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	200	Gal	Tack Coat
407B000	5	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	2,534	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A366	5,853	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	150	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	400	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
430B043	1,775	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 49,000.00)
701A231	10	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	9	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	2	Mile	Broken Temporary Traffic Stripe
701C001	17	Mile	Solid Temporary Traffic Stripe
703A002	1,157	SQFT	Traffic Control Markings, Class 2, Type A
703D001	480	SQFT	Temporary Traffic Control Markings
705A032	16	Each	Pavement Markers, Class A-H, Type 1-B
705A037	590	Each	Pavement Markers, Class A-H, Type 2-D
740B000	494	SQFT	Construction Signs
740O000	1	Each	Pilot Car