

**Alabama Department of Transportation
Proposal Item Summary**

070. 99-408-663-265-005

WILCOX COUNTY

Contract Time: 35 Working Days

for constructing the Slide Repair on SR-265 (Eastbound Roadway and Westbound Roadway) from 0.100 mile south of the junction of Church Road southeast of Camden. Length 0.094 mi.

The Bracket Estimate on this project is from \$488,654 to \$597,244.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 8,000.00 Per Acre) (Approximately 1 Acre)
206D000	68	LF	Removing Pipe
210A000	7,500	CUYD	Unclassified Excavation
210D013	8,500	CUYD	Borrow Excavation (A-4(0) or Better)
230A000	4	RBST	Roadbed Processing
401A000	1,083	SQYD	Bituminous Treatment A
405A000	264	Gal	Tack Coat
408A052	475	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A341	129	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B636	157	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424C340	192	Ton	Superpave Bituminous Concrete Base Layer, 1" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	1	Mile	Scoring Bituminous Pavement Surface
430B043	260	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
602A000	4	Each	Right Of Way Markers
606A000	400	LF	6" Underdrain Pipe
610D003	200	SQYD	Filter Blanket, Geotextile
650A000	250	CUYD	Topsoil
652A100	1	Acre	Seeding
654A000	200	SQYD	Solid Sodding
656A010	1	Acre	Mulching
665B001	3	Ton	Temporary Mulching
665E000	3,000	SQYD	Polyethylene
665F000	500	Each	Hay Bales
665G000	500	Each	Sand Bags
665J002	2,000	LF	Silt Fence
665N000	100	Ton	Temporary Coarse Aggregate,ALDOT Number 1
665O001	2,000	LF	Silt Fence Removal
665Q002	300	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 39,500.00)
701E000	2,000	LF	Solid Temporary Traffic Stripe
701G253	1,000	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701G265	1,000	LF	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
705A030	99	Each	Pavement Markers, Class A-H, Type 2-C
705A037	13	Each	Pavement Markers, Class A-H, Type 2-D
710A165	60	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background, Fluorescent)

Item No.	Quantity	Units	Description
710B021	126	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
710C000	1	LS	Removal Of Existing Roadway Signs
740B000	418	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740F002	10	Each	Barricades, Type III
742A001	2	Each	Portable Changeable Message Sign, Type 2