

**Alabama Department of Transportation  
Proposal Item Summary**

**018. IM-1065(516)**

**BUTLER COUNTY**

Contract Time: 50 Working Days

for constructing the Pavement Preservation (Resurfacing and Traffic Stripe) on I-65 from the CR-41 Overpass to 1.000 mile south of the Lowndes County Line. Length 7.249 mi.

The Bracket Estimate on this project is from \$2,451,158 to \$2,995,860.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
410H000	1	Each	Material Remixing Device
420A015	10,695	Ton	Polymer Modified Open Graded Friction Course
420B000	54,650	Gal	Open Graded Friction Course Tack Coat
424B283	150	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range E
424B287	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range E
432A000	122,900	SQYD	High Density Mineral Bond
534A000	195	Each	Cleaning Pipe Underdrain Outlets
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 144,000.00)
701A227	15	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	15	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	15	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	2,550	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	15	Mile	Broken Temporary Traffic Stripe
701C001	30	Mile	Solid Temporary Traffic Stripe
701F000	2,550	LF	Dotted Temporary Traffic Stripe
701G142	2,110	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	2,110	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	2,110	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	4,220	LF	Solid Traffic Stripe Removed (Plastic)
701H006	2,110	LF	Broken Traffic Stripe Removed (Plastic)
703A002	5,385	SQFT	Traffic Control Markings, Class 2, Type A
705A030	1,010	Each	Pavement Markers, Class A-H, Type 2-C
705A031	13,320	Each	Pavement Markers, Class A-H, Type 1-A
705A032	875	Each	Pavement Markers, Class A-H, Type 1-B
740B000	1,872	SQFT	Construction Signs
740C000	24	SQFT	Special Construction Signs
740D000	500	Each	Channelizing Drums
740E000	275	Each	Cones (36 Inches High)
740M001	275	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	8	Each	Portable Changeable Message Sign, Type 2